

Trading Copier

Installation Guide + Complete User Manual

Version 0.16.8 / Windows and macOS
Written for first-time investors and first-time copier users
Revised 28 August 2026 / clearer live chart context

START HERE

How to use this manual

This book has two jobs. Part One gets the copier installed and connected. Part Two teaches you how to operate it safely every day. The later chapters explain the trading language and every signal type so a new investor can understand what the screen means before approving anything.

A screenshot shows the real program. A chart is an educational drawing of a setup, not a promise that price will follow the drawing.

The safest learning order

1. Read Trading basics before approving an options trade.
2. Install and complete the five setup steps.
3. Stay in Approve first mode and use the smallest practical risk.
4. Confirm the private connection check and Schwab account before market hours.
5. Learn the Signal Types page. Turn off anything you do not understand.
6. Use practice mode and a synthetic entry/exit before live execution.
7. Open the Alerts page once after installing, and read the What is new chapter if you are updating.

Nothing in this manual is investment advice or a guarantee. A technically correct copier can still execute a losing trade. Options can lose 100% of their value.

Contents

How to use this manual 2

The safest learning order . . . 2

Contents 3

What is new in version 0.16.8 10

EMA and VWAP are drawn on the live chart . . . 10

Supply and demand use completed Schwab bars . . . 10

An open trade shows its underlying geometry . . . 10

What is new in version 0.16.7 11

The flat-account message now gives a definite answer . . . 11

A completely flat Schwab account can now reconcile . . . 11

Schwab, not the local database, authorises a sell . . . 11

The health screen now reports read quality . . . 11

What is new in version 0.16.4 12

Settings no longer compete with positions and orders . . . 12

What is new in version 0.16.3 13

Alerts and approvals now appear by themselves . . . 13

One database is now the source of truth . . . 13

What is new in version 0.16.0 14

Your positions are watched all day, not just at startup . . . 14

One position it does not recognise no longer stops everything . . . 14

Faster signals, and a clock you cannot miss 15

Andre's trades reach you in seconds instead of minutes . . . 15

A trade waiting for you is now impossible to miss . . . 15

Alerts, unconfirmed orders, and what to do now 16

A new Alerts page, and nothing fails quietly . . . 16

An order Schwab never confirmed can now be settled . . . 16

A rare way to sell too much is closed . . . 16

What you should do differently . . . 16

What the copier does - and does not do 17

Eligible messages . . . 17

What stays private . . . 17

Trading basics for a first-time investor 18

Stocks, shares, and options . . . 18

The five prices you must recognize . . . 18

Risk, R, and position size . . . 18

Orders, fills, exits, and uncertainty 19

An alert is not the same thing as a fill . . . 19

Why uncertain means stop and inspect . . . 19

Short-term versus long-term . . . 19

Install on Windows 20

Before downloading . . . 20

Download and install . . . 20

Practice mode . . . 20

Install on a Mac 21

Choose the correct Mac . . . 21

Download and run . . . 21

Create the required Schwab developer app 22

Before starting . . . 22

Schwab portal - create the developer account 23

If registration does not finish . . . 23

Schwab portal - create the Trader API app 24

Wait for approval, then find the App Key and Secret 25

How to tell the two values apart . . . 25

Put the Schwab credentials into the copier 26

Now authorize the brokerage account . . . 26

Run the safe order check . . . 26

Schwab key problems and safe fixes 27

The five setup screens 28

1. Connect to Andre . . . 28
2. Connect Schwab . . . 28
3. Choose account . . . 28
4. Your limits . . . 28
5. Finish . . . 28

Update without exchanging keys again 29

Home screen 30

What to look for . . . 30

Approvals screen 31

What to look for . . . 31

The clock on a waiting trade 32

Two deadlines, one countdown . . . 32

How it escalates . . . 32

If one expires unanswered . . . 32

Who presses the button 33

Automatic takes two deliberate actions, not one . . . 33

If you are away, there are gentler options first . . . 33

Short Term screen 34

What to look for . . . 34

When Short Term asks you a question 35

A position it does not recognise . . . 35

An order Schwab never confirmed . . . 35

What each position status means 36

Signal Types screen 37

What to look for . . . 37

The Alerts page 38

Is it running? . . . 38
Checking your Schwab account . . . 38
Signals from Andre . . . 38
Everything, newest first . . . 38

Opening Range Breakout (Simple 2R) 39

The idea in one sentence . . . 39

Andre ORB (no TP, -20% premium stop) 41

The idea in one sentence . . . 41

Opening Range Breakout (5m RVOL, Legacy) 43

The idea in one sentence . . . 43

ORB v2 (Break-Confirm-Retest) 45

The idea in one sentence . . . 45

Andre's Ladder 47

The idea in one sentence . . . 47

EMA/VWAP Cross 3min 49

The idea in one sentence . . . 49

SMC (Sweep -> MSS -> FVG Retrace) 51

The idea in one sentence . . . 51

SMC 15m (Sweep -> MSS -> FVG Retrace) 53

The idea in one sentence . . . 53

SMC Swing 1H (Sweep -> MSS -> FVG, multi-day) 55

The idea in one sentence . . . 55

Liquidity Flow (sweep vs acceptance) 57

The idea in one sentence . . . 57

VWAP Trend Pullback 59

The idea in one sentence . . . 59

VWAP Mean Reversion 61

The idea in one sentence . . . 61

Liquidity Sweep and Reclaim 63

The idea in one sentence . . . 63

Intraday Compression Breakout 65

The idea in one sentence . . . 65

Order Flow Momentum 67

The idea in one sentence . . . 67

1H Level + Flow Reversal 69

The idea in one sentence . . . 69

Late-Day Momentum Continuation 71

The idea in one sentence . . . 71

Gamma Level Reaction 73

The idea in one sentence . . . 73

KayCapitals A+ ORB Continuation 75

The idea in one sentence . . . 75

Swing — Trend Pullback 77

The idea in one sentence . . . 77

Swing — 52-Week High Breakout 79

The idea in one sentence . . . 79

Long Term overview 81

What to look for . . . 81

Long Term tools and research 82

What to look for . . . 82

Long Term actions in plain language 83

Optional AI . . . 83

Position Doctor permissions and publisher close-only 84

The subscriber chooses exactly what may run . . . 84

Andre's master access switch . . . 84

Set up optional AI for Long Term 85

Choose one setup . . . 85

Find the controls in the copier . . . 85

OpenAI setup 86

What success looks like . . . 86

Anthropic setup 87

Ollama local setup 88

Use AI safely and control cost 89

Start with a one-ticker test . . . 89

Understand the bill before a watchlist scan . . . 89

The LLM cannot authorize a trade . . . 89

Protect and replace the key . . . 89

LLM troubleshooting 90

My Results 91

What to look for . . . 91

System Map 92

What to look for . . . 92

Daily, weekly, and emergency routines 93

Before the market each day . . . 93

Every week . . . 93

If something looks wrong . . . 93

Emergency takeover and flatten 94

Take manual control . . . 94

Emergency flatten . . . 94

Live View - watch what the copier sees 95

What the screen shows . . . 95

The one button: Take Profit . . . 95

If something looks wrong . . . 96

Atomic multi-leg option groups 97

Current release boundary . . . 97

Safety rules that cannot be bypassed . . . 97

Supported structures and leg map 98

Two-leg diagram . . . 98

Four-leg diagram . . . 98

Net prices, actions, and risk display 99

What the group card shows . . . 99

Multi-leg workflow and status runbook 100

Common rejection and recovery cases . . . 100

Live controls and broker capability matrix 101

Required local switches . . . 101

Restart, partial fill, and quarantine recovery 102

Automatic restart drill . . . 102

Partial fills . . . 102

Durable acknowledgement milestones . . . 102

Qualification checklist before real money 103

Troubleshooting 104

Glossary 105

Security and support checklist 106

Never share . . . 106

Safe to share for support . . . 106

Local storage . . . 106

Authoritative investor references 107

READ THIS FIRST IF YOU ARE UPDATING

What is new in version 0.16.8

Live View now carries more of the market context visible in Andre's main application, while remaining a read-only window that cannot create a trade.

EMA and VWAP are drawn on the live chart

The chart now draws the 9-period EMA, 21-period EMA, and regular-session VWAP from the same real five-minute Schwab candles displayed on screen. Use the **EMA · VWAP** button to hide or show all three overlays.

Supply and demand use completed Schwab bars

Green demand and red supply bands are derived conservatively from completed one-hour and four-hour structure. Missing or partial Schwab history stays unknown: the copier does not invent a zone or erase the last known zone because one market-data response was empty.

An open trade shows its underlying geometry

When Andre's signal provides them, Live View now shows the underlying entry, stop, and target as labelled chart levels and as separate rows in the Open trade card. These are kept separate from the option premium paid and the broker's option-premium protective stop.

New positions save the three underlying values so Live View can restore them after a copier restart. A position opened by an older version may not contain those saved values; the screen says they were not provided instead of estimating them.

EARLIER UPDATE

What is new in version 0.16.7

This update fixes the flat-account case reported by a subscriber, makes the account-readiness message unambiguous, and adds a broker-authority check before any single-position sale or protective-stop replacement.

The flat-account message now gives a definite answer

During checks one and two, the copier now says explicitly that flat-account confirmation **does not pause new buying**. It separately explains that sell and protective-stop orders require Schwab to confirm an existing holding. After check three, a new resolution alert says the account is confirmed flat and that reconciliation is not blocking new entries. Home separately reports signal-list connectivity and any other entry block; your Settings, approval choice, and risk rules still apply.

A completely flat Schwab account can now reconcile

When an account holds nothing, Schwab may omit the requested **positions** field instead of returning an empty list. Older versions treated that answer as permanently unknown, so positions closed in Schwab could remain open on the copier screen forever.

The copier now recognises a complete cash-only account response as a possible flat account. It still does not trust one response: the same absence must be observed on three separate checks, and those confirmations are stored in the database so restarting cannot erase the evidence. Empty, malformed, partial, and non-cash responses still change nothing.

Schwab, not the local database, authorises a sell

Before Close, Sell everything, an automatic exit, or a replacement protective stop can touch an order, the copier takes a fresh position read. Schwab must confirm the exact long holding and at least the quantity the copier plans to act on. If Schwab does not list it, lists less, reports a short holding, or gives an unreadable answer, no stop is cancelled and no order is sent.

A blocked order appears as an important alert. Let custody reconcile the row and verify the account in the Schwab app; do not keep pressing Close.

The health screen now reports read quality

A custody thread can be alive while every account comparison is being refused. The Alerts page now distinguishes a possible flat account from a failed read, shows sustained failure streaks as unhealthy, and rolls repeated copies of the same unread alert into one row with a count and last-seen time.

EARLIER UPDATE

What is new in version 0.16.4

This update hardens the copier against the database lock and stale-process problems that can occur when multiple parts of a trading app save at the same time. Your existing settings are moved automatically; no values need to be entered again.

Settings no longer compete with positions and orders

Preferences, Done for the day, emergency/manual control, and the last account-value preview now live in a dedicated **settings.db**. Positions, approvals, alerts, and order records remain in **state.db**. A burst of trading activity therefore cannot block a settings save, and a settings save cannot delay position custody or an exit.

1. Version 0.16.3 settings are copied from state.db exactly once after a backup is created.
1. Both databases use serialized WAL startup, a 15-second lock wait, full durability, and an integrity check.
1. If a second, older copy of the copier tries to overwrite settings saved by a newer copy, its stale save is refused and nothing is overwritten.
1. If settings.db is damaged, the copier reports the problem and does not silently revive an old JSON snapshot.

Install the update with every copier window closed. After it starts, your usual settings should already be present. Secrets remain in the operating-system password vault and are never moved into either database.

EARLIER UPDATE

What is new in version 0.16.3

This update makes the screen follow the running copier without asking you to refresh it, and moves the copier's local preferences and control flags into its existing database. Your identity, Schwab connection, limits, open-position history, and choices are preserved automatically.

Alerts and approvals now appear by themselves

While any copier page is open, it checks the local app for changes every few seconds. A newly waiting approval or important alert updates the number in the navigation and refreshes the page that needs your attention. Returning to the browser tab also checks immediately. You no longer have to reload the page or switch tabs just to discover that the copier is waiting for you.

One database is now the source of truth

Older versions kept preferences and a few safety controls in separate JSON files. Those files could survive an upgrade with values that no longer matched what the running app believed. Version 0.16.3 imports them once into **state.db**, then uses database transactions for every later save. The old files are left untouched as rollback snapshots and cannot override newer settings after a restart.

1. Settings saved in the browser survive a restart from the database.
1. Done for the day, emergency/manual control, and the last account-value preview use the same database authority.
1. A pre-upgrade backup includes both databases and every legacy settings/control file before anything is imported.
1. Passwords, OAuth tokens, and private keys still stay in the operating-system password vault; they are not moved into the settings database.

Nothing for you to convert by hand. Install the update with the copier closed, open it normally, and then confirm your usual limits on Settings.

READ THIS FIRST IF YOU ARE UPDATING

What is new in version 0.16.0

This release is about two things: not losing track of what you own, and getting Andre's trade in front of you fast enough for it to still be worth taking. Every change below happens on its own once the new version is installed. Nothing you set up before has to be done again - your device identity, private key, Schwab app details, chosen account, limits, and history are all preserved.

Install this version before the market opens. The problems described on this page and the two after it can still happen to anyone running an older one.

Your positions are watched all day, not just at startup

The old version compared your Schwab account against its own records once, at startup, and acted on the first answer it received. If that one answer came back without your positions in it, it concluded you were holding nothing and quietly forgot trades you were still in. Those trades were then left with no protective stop and nothing watching them.

It now re-checks every 30 seconds for as long as it is running. It will not act on a reply from Schwab that never carried position information at all, and it has to see the same position missing three separate times before it believes it is really gone. If a protective stop has disappeared from something you hold, it places a new one and tells you it did.

Nothing for you to do. Home and the new Alerts page both show a panel called **Checking your Schwab account** with how many checks have run, how many stops were confirmed, and any stop the program had to put back.

One position it does not recognise no longer stops everything

If the old version found a holding in your Schwab account it could not match to one of Andre's trades - shares you bought yourself, or a contract left over from something else - it stopped. Worse, it also stopped selling, on every other position you held, and restarting did not help. That was the most dangerous fault in the program and it is the reason this release exists.

Now an unrecognised holding pauses **new buying only**. Everything the program opened itself keeps being looked after: stops, targets, and closing when Andre closes all keep running normally. Only opening something new is on hold, and you can end that hold yourself with a button - see the chapter on the Short Term page later in this manual.

Faster signals, and a clock you cannot miss

Andre's trades reach you in seconds instead of minutes

Two invisible delays were costing you time. A cache on the internet between Andre and your computer could hand the program a five-minute-old "nothing new" without either side noticing, and a single queue of work meant one slow sale held up every new trade behind it. Both are fixed, and the program now checks for new trades five times more often than it used to.

This matters for one reason. The program refuses to open one of Andre's fast trades more than about fifteen minutes after he took it, because buying a move that has already happened is a different trade from the one he is in, and usually a losing one. Every minute lost getting the message to you was coming out of your window to answer it.

A trade waiting for you is now impossible to miss

Unless you have deliberately turned on automatic buying, nothing is bought until you press Approve. The only prompt used to be a desktop notification - easy to miss, invisible on a locked screen, and silently dropped when the computer is busy. Somebody sat through a fifteen-minute window and came back to a trade that was no longer buyable.

1. A banner now appears at the top of **every page** of the program, above everything else, for as long as a trade is waiting.
1. It carries a live countdown to the real deadline - whichever runs out first, your own answer window or the moment the trade becomes too old to buy.
1. It escalates. The colour, the wording, and how often it makes a noise all change as the clock runs down. Under two minutes it becomes an alarm.
1. The countdown also appears in the browser tab title, so a minimised window still shows it.
1. If your browser is blocking sound, the banner says so and offers a button to switch it on, rather than staying quietly silent.
1. If a trade does expire unanswered, the program tells you afterwards, with the symbol and the strategy. Nothing was bought and no money was lost - but you find out, instead of the day passing in silence.

Alerts, unconfirmed orders, and what to do now

A new Alerts page, and nothing fails quietly

Anything worth telling you is now written down first and shown to you second, so a notification that never reached your screen costs you the pop-up and not the fact. Alerts survive closing and reopening the program, which the old ones did not - and that mattered most when the message being lost was the one explaining why a restart was needed. Important ones stay on screen until you tick them off.

The same page answers a question no screen could answer before: **is it actually running?** The program is now several separate parts that fail independently, each listed with what you lose if it stops. A quiet screen is no longer indistinguishable from a quiet market.

An order Schwab never confirmed can now be settled

Sometimes an order is sent and Schwab never confirms whether it was accepted. The program will not retry, because retrying could buy or sell the same thing twice. That row used to sit there forever: it was not watched, the Close button refused it, and it quietly held on to part of the money you had set aside to trade with. Short Term now offers three answers - **Ask Schwab**, **Yes, I own it**, and **No, it never went through** - and none of them buys or sells anything.

A rare way to sell too much is closed


When the program works a sale down in steps to get a better price, a step that partly filled before being replaced was not being counted, so the next step could offer the full size again. On an option that could leave you short a contract you never meant to sell. Every step is now sized to what is actually left.

What you should do differently

1. Install this version, then open **Alerts** once and read what is there.
2. Each morning, check that every part listed under **Is it running?** says Running.
3. If Short Term asks you about a position it does not recognise, answer it. Nothing new is bought until you do.
4. Read the trade-off on the Settings page before deciding whether to keep approving every trade by hand. If you copy Andre's intraday scalps and you are not at this computer at 9:30, approving by hand will cost you most of them.
5. Everything else stays the same. Approve first is still the default, and it is still what this manual recommends for a beginner.

What the copier does - and does not do

The Trading Copier watches a private signal feed, verifies that a message really came from Andre, checks that the exact device is allowed to receive that strategy, applies the subscriber's own limits, and then either asks for approval or submits the order when automatic execution has been separately enabled.



Paper trades and Long Term actions do not enter this signal path.

The private key and Schwab credentials never leave the subscriber's computer.

Eligible messages

1. Only a new **live, filled, short-term** trade is published as an entry signal.
1. Paper activity is ignored.
1. Long Term activity is independent and is not copied.
1. A private connection check can confirm one device without creating an order.
1. Exits continue for an already accepted copied position even if that strategy is later turned off.

What stays private

1. Schwab username and password
1. Schwab developer app secret
1. The copier's private encryption key
1. Account balances and positions
1. The subscriber's local limits and muted signal types

Trading basics for a first-time investor

Stocks, shares, and options

Term	Plain-language meaning
Stock / share	A small ownership unit in a company or fund. One share rises or falls dollar-for-dollar with its quoted price.
Call option	A time-limited contract that generally gains value when the underlying rises. Buying a call does not guarantee a profit even when the stock rises.
Put option	A time-limited contract that generally gains value when the underlying falls.
Contract	One standard equity-option contract usually represents 100 shares. A quoted premium of $1.25 normally costs about $125 before fees.
Expiration	The last date the option exists. A 0DTE option expires the same trading day and can lose value extremely quickly.

The five prices you must recognize

1. **Bid:** the highest displayed price a buyer currently offers.
1. **Ask:** the lowest displayed price a seller currently offers.
1. **Spread:** ask minus bid. A wide spread increases slippage and makes exits harder.
1. **Entry:** the price at which the trade is opened.
1. **Stop and target:** the planned loss exit and profit exit. Neither guarantees that an order fills at exactly that price.

Example: an option quoted $1.20 bid / $1.30 ask has a $0.10 spread. Buying one contract near $1.30 is about $130. If it falls to $0.65, the position has lost about $65, or 50%, before fees.

Risk, R, and position size

Many strategy explanations use **R**. R is the planned distance from entry to stop. If the entry is $100 and the stop is $98, then 1R is $2 per share. A 2R target is $104. The copier's risk percentage and buying-power checks still decide the actual order size.

Never assume a stop limits the loss perfectly. A gap, halt, fast option market, rejected order, expired authorization, or lost connection can produce a worse result.

Orders, fills, exits, and uncertainty

An alert is not the same thing as a fill

1. A **signal** is the publisher's instruction.
2. An **approval** is your permission for the copier to continue.
3. An **order** is the request sent to Schwab.
4. A **fill** means Schwab reports that some or all of the order executed.
5. A **position** is what the broker says you now own.

Why uncertain means stop and inspect

A network interruption can happen after Schwab receives an order but before the copier receives the reply. Retrying blindly could double the position. When the copier says an order is uncertain, open Schwab and inspect Orders and Positions before taking another action.

Short-term versus long-term

Short Term	Long Term
Starts from eligible live signals	Independent of signals
Usually minutes, hours, or a few days	Portfolio work measured in weeks, months, or longer
Shown on Short Term and Approvals	Shown in the separate Long Term area
Publisher exits can close an accepted copied position	You create and approve your own buy, add, trim, exit, or covered-call proposal

Install on Windows

Before downloading

1. Use Windows 10 or 11, 64-bit.
2. Install pending Windows updates.
3. Make sure the computer's Date & Time is automatic.
4. Use a Windows account you control and can sign into.

Download and install

1. Open https://dre15w1.github.io/trading-copier-install/.
2. Read the disclosures and agreement, then choose **Download for Windows**.
3. Open Downloads and double-click **Trading-Copier-Setup.exe**.
4. If SmartScreen appears, confirm the filename and official source, choose **More info**, then **Run anyway**.
5. Complete the installer. Use the Trading Copier shortcut in the Start menu or on the desktop.
6. The browser opens the local address shown by the app. 127.0.0.1 means this computer, not a public website.

Do not download a copy sent through email, text, or an unfamiliar file-sharing link. Use the official page every time.

Practice mode

```
& "$env:LOCALAPPDATA\Programs\Trading Copier\Trading Copier.exe" --dry-run
```

Practice mode exercises the workflow but does not submit real orders. Confirm the practice banner is visible.

Install on a Mac

Choose the correct Mac

1. Apple menu > About This Mac.
2. If Chip begins with Apple M, download Apple Silicon.
3. If Processor mentions Intel, download Intel.

Download and run

```
if [ "$(uname -m)" = "arm64" ]; then
FILE="$HOME/Downloads/copier-agent-macos-apple-silicon"
else
FILE="$HOME/Downloads/copier-agent-macos-intel"
fi
chmod +x "$FILE"
xattr -d com.apple.quarantine "$FILE"
"$FILE"
```

1. Download exactly once so the filename does not gain a (1) suffix.
2. Open Terminal from Applications > Utilities.
3. Paste the full block and press Return.
4. Leave the copier running. Closing only the browser tab does not quit it.
5. Use the Quit Copier link in the footer when you intend to stop the program.

A certificate warning from the copier's time check is not a trading signal. Update macOS, verify automatic Date & Time, and restart. Do not rely on a custom entry-hours window until the warning clears. Exits are never blocked by the clock.

Create the required Schwab developer app

Every subscriber uses their own Schwab developer application. Andre's Schwab key is never entered into the subscriber copier. The developer application is what allows the copier on this computer to ask Schwab for permission to place orders in the account the subscriber chooses.

The developer account and the ordinary brokerage account are related but separate logins. Creating a developer account does not move money, open a trade, or give Andre access.

ITEM	WHERE IT COMES FROM	WHERE IT GOES
Schwab username + password	Already owned by subscriber	Typed only on Schwab's website
App Key / Client ID	Created in Schwab Developer Portal	Pasted into this subscriber's copier
Secret / Client Secret	Created in Schwab Developer Portal	Pasted once; never sent to Andre
TV1- connection code	Created by the copier	The only code sent to Andre

The Secret is treated like a password. The TV1- code is the only one of these four items designed to be sent to Andre.

Before starting

1. Have access to the email address used for Schwab developer registration.
2. Know the subscriber's normal Schwab brokerage login, but do not send it to Andre.
3. Use the same computer that will run the copier when entering the App Key and Secret.
4. Write down the exact callback URL from this manual before creating the app.

Schwab portal - create the developer account

Official starting address: **https://developer.schwab.com/**. Type or bookmark this address directly. Do not follow an API-key link sent by an unknown person.

1. Open the official Schwab Developer Portal.
2. Choose the registration or sign-up option for an **Individual** developer account.
3. Enter the requested contact information and email address.
4. Open Schwab's verification email and complete the verification link.
5. Return to the Developer Portal and sign in.
6. If Schwab presents terms or an API agreement, read and accept them only for the subscriber's own account.

The portal's button names can change slightly. Look for the path that ends at the signed-in developer dashboard and a page named **My Apps**, **Apps**, or similar. Do not use the regular schwab.com brokerage page to look for an App Key; it is created in the Developer Portal.

If registration does not finish

1. Check spam or junk mail for the verification message.
2. Make sure the verification link is opened in the same browser session.
3. Turn off aggressive popup blocking for developer.schwab.com only.
4. If the portal says the email already exists, use its password-recovery flow instead of creating duplicates.

Schwab portal - create the Trader API app

After signing in, open **My Apps** and choose **Create App**, **Add App**, or the equivalent new-application button.

Field	What to enter
Application type	Individual / personal use, when the portal asks
Product	Trader API / Accounts and Trading Production; add Market Data Production only if the portal offers or requires it
App name	A simple personal name such as Jane Trading Copier
Callback URL	https://127.0.0.1:8182/callback, character for character
Description	Personal trading automation for my own self-directed account

1. Select the Trader API or Accounts and Trading product used for an individual brokerage account.
2. Enter a personal app name. It does not need to match the copier device name.
3. Paste the callback URL exactly as shown in the table.
4. Enter the personal-use description.
5. Review every field, then submit the app for Schwab's review.

A trailing slash, localhost instead of 127.0.0.1, http instead of https, a different port, or a spelling change can break authorization. Use exactly **https://127.0.0.1:8182/callback** unless the copier itself displays a different callback during setup.

Wait for approval, then find the App Key and Secret

Submitting the app does not mean it is ready immediately. Return to My Apps and watch the status. Schwab may use wording such as Pending, In Review, Approved, or Ready for Use.

1. Do not repeatedly delete and recreate a pending app; that can restart the process.
2. Wait until Schwab marks the app **Ready for Use** or otherwise approved for production.
3. Open the approved app's detail page.
4. Locate the value labeled **App Key**, **Client ID**, or equivalent. These names refer to the public identifier the copier calls App Key.
5. Locate the value labeled **Secret**, **Client Secret**, or equivalent.
6. Use the portal's reveal or copy control if the Secret is hidden. Copy it carefully without spaces before or after it.

Some portals show a Secret only once or require a regenerate action later. Save it directly into the copier rather than an email, text message, shared note, or screenshot.

How to tell the two values apart

App Key / Client ID	Identifies which developer app is requesting access. Enter it in the copier's App Key box.
Secret / Client Secret	Proves the app is allowed to make that request. Enter it in the copier's Secret box. Never send it to Andre.

Neither value is the subscriber's Schwab password. Neither value is the TV1- connection code.

Put the Schwab credentials into the copier

1. Open the Trading Copier and continue to setup step 2, **Connect Schwab**.
2. In **App Key**, paste the portal's App Key or Client ID.
3. In **Secret**, paste the portal's Secret or Client Secret.
4. In **Callback URL**, confirm the address matches the approved developer app character for character.
5. Press **Save app details**.
6. The Secret moves into this computer's password vault. The copier does not display it again.

Do not paste the short fingerprint, TV1- code, Schwab password, or Andre's key into either Schwab credential field.

Now authorize the brokerage account

1. Press **Connect Schwab**.
2. A browser opens Schwab's own sign-in page.
3. Enter the subscriber's normal Schwab username and password on Schwab's page, not inside the copier.
4. Review the authorization request and approve it.
5. Return to the copier. It should show **Schwab is connected** and allow the subscriber to continue to account selection.
6. If the browser does not return, copy the entire address from the browser after authorization and paste it into the copier's recovery box.

A green **Schwab is connected** message is the authoritative status. The Connect Schwab button may remain available because it is also the way to reconnect later; its presence does not mean the connection failed.

Run the safe order check

1. Open **Settings**, find **Safe order check**, and press **Run safe order check**.
1. The copier asks Schwab to validate a one-share SPY market-order preview against the selected account.
1. The preview does not submit an order, cannot fill, and cannot change a position.
1. A pass confirms that Schwab accepted that account and order request at that moment. It does not guarantee that a later live order will fill or avoid a broker rejection.

Schwab key problems and safe fixes

Problem	What to check
Connect button disabled	Save both App Key and Secret first.
Invalid client / unauthorized_client	Confirm the App Key belongs to the approved app and was copied without spaces.
Invalid secret	Return to the approved app, copy the Client Secret again, or use Schwab's regenerate process and replace the saved Secret.
Redirect or callback mismatch	Compare scheme, 127.0.0.1, port 8182, /callback, capitalization, and trailing slash character for character.
App still pending	The key cannot be used for production until Schwab approves it. Wait rather than recreating it.
Browser warning on callback	The callback is this computer. Follow the copier's recovery instructions and paste the entire callback URL if automatic return fails.
Connected, but expires soon	Reconnect through the copier. Schwab normally requires periodic reauthorization.
Changed or regenerated Secret	Save the new Secret in the copier, then reconnect Schwab. Do not change the TV1- device identity.

Support may ask for a screenshot of the portal status or callback setting. Black out the App Key, Secret, account numbers, authorization code, and personal information first. Never send the Secret even to Andre.

The five setup screens

1. Connect to Andre

1. The copier creates a private/public key pair on this computer.
2. Press Copy code and send the complete TV1- connection code to Andre.
3. The TV1- code contains the device ID and public key only. The private key stays on this computer.
4. Andre links the exact device and sends a private non-trading connection check.
5. When the screen says Connected to Andre, it advances automatically.

2. Connect Schwab

1. Save your own App Key, Secret, and exact callback URL.
2. Press Connect Schwab. Sign in only on Schwab's website.
3. Approve access and return to the copier.
4. If the browser cannot return, paste the entire callback address into the recovery field.

3. Choose account

Select the intended masked account. Other Schwab accounts are left alone.

4. Your limits

Begin with a small risk percentage, a low maximum number of open positions, a daily loss limit, and Approve first.

5. Finish

Verify Signal connection, masked Schwab account, risk limits, approval mode, and password-vault status before pressing Start watching for signals.

Update without exchanging keys again


A normal update installs over the old app and preserves the .trading-copier data folder, device identity, private key, Schwab app details, selected account, limits, and history on both Windows and Mac.

1. Quit the running copier from its footer.
2. Download the latest build for the same operating system and Mac architecture.
3. Install or launch the replacement normally.
4. Confirm Home shows Connected to Andre and the expected masked Schwab account.
5. Send a new TV1- code only for a new computer or when the app explicitly requires relinking.

> Do not choose Create a brand new key during a routine update. That deliberately creates a new identity and requires Andre to link it.

SCREEN WALKTHROUGH

Home screen




Home is the daily health check: signal connection, Schwab authorization, today's activity, and immediate controls.

What to look for

1. Signals from Andre should say Connected and show a recent check.
2. Schwab should say Connected and show the intended masked account.
3. Watch the reconnect countdown; Schwab authorization lasts about seven days.
4. Review open count, realized result, and approval mode.
5. Done for the day blocks new entries; it does not abandon exits.
6. **Is it running?** lists the parts of the program. Every part that matters should say Running before you rely on it.
7. **Checking your Schwab account** is the running score of the every-30-seconds comparison against your real holdings. Positions with no stop should be zero.
8. Version 0.16.0 added those two panels below the ones in this picture.

SCREEN WALKTHROUGH

Approvals screen



Approvals is where a new entry waits when Approve first is enabled.

What to look for

1. Read symbol, call/put direction, strategy, instrument, quantity, and maximum cost.
2. Compare the planned stop and target with the amount you can afford to lose.
3. Watch the countdown at the top right of each trade. It runs to whichever deadline comes first.
4. Approve only when you understand the trade; otherwise press No thanks.
5. Doing nothing is a decision too: at zero the request is thrown away and nothing is bought.
6. After approval, wait for the broker result. Do not click repeatedly.
7. If status becomes uncertain, inspect Schwab before doing anything else.

The clock on a waiting trade

When you approve every trade yourself, nothing at all is bought until you press the button. Version 0.16.0 makes that wait loud, because the previous version made it silent and somebody lost a trade to it.

Two deadlines, one countdown

There are two separate clocks on any waiting trade, and the countdown you see always runs to whichever one runs out first.

Clock	What happens when it reaches zero
Your answer window	Set on the Settings page, in seconds, between 30 and 3600; the program starts at five minutes. At zero the request is thrown away and nothing is bought. Nothing is charged and nothing is lost - you simply do not take the trade.
Too old to buy	About fifteen minutes after Andre took the trade, whatever your answer window says. After that the request may still be on screen, but pressing Approve does nothing at all, because buying a move that has already happened is a different and usually losing trade.

Making your answer window longer does not make a trade buyable for longer. It only means the request sits on screen after it has stopped being able to do anything.

How it escalates

1. A banner appears at the very top of every page in the program, above everything else on that page.
1. The countdown ticks down on screen and in the browser tab title, so a minimised window still shows it.
1. It makes a sound, more often and with more notes the closer it gets to zero.
1. Under two minutes the banner turns into an alarm and the wording changes to say so.
1. At zero it says the trade was missed, and stops.

Browsers refuse to play a sound on a page nobody has clicked on yet. When that happens the banner says so and shows a **Turn the alert sound on** button. Press it once, early in the day, rather than finding out at 9:31 that the alarm was mute.

If one expires unanswered

The program now tells you afterwards, on every page, with the symbol and the strategy: you missed a trade today, nothing was bought, and you have not lost any money - but Andre took it and you did not. That message stays until you tick it off. Before this release the row simply vanished and nothing anywhere said what had happened.

Who presses the button

This is the most consequential setting in the program. It is on the **Settings** page under **Who presses the button**. Version 0.16.0 rewrote that section to state the real cost of both choices, because there is no option here with no downside.

Choice	What it costs you
I approve every trade (the default, and recommended)	Nothing is bought unless you press Approve, so you can never lose money on a trade you did not see. But you have to be at this computer, inside your answer window, every time Andre trades. When you are driving, in a meeting, or asleep, you do not get the trade at all.
Buy automatically without asking me	You get every trade Andre takes, on time, whether or not you are watching. But real money leaves your account with no human check, and a bad day happens at full speed while you are asleep. Your limits still apply - position size, the maximum number of open positions, and the daily loss limit are all still enforced - but nobody looks at the trade before it happens.

The honest version, in one sentence: if you copy Andre's intraday scalps and you are not sitting at this computer at 9:30 in the morning, approving every trade by hand will cost you most of them. Pick the option whose bad day you would rather have.

Automatic takes two deliberate actions, not one

Choosing automatic on its own does nothing. There is a separate tick-box saying you understand that orders will be placed with real money while you are not watching. Without that tick, automatic buying stays switched off and you are still asked to approve each trade - and the Settings page says so out loud rather than leaving you to discover it on a quiet morning.


If you are away, there are gentler options first

1. Turn off the signal types you do not want, on the Signal types page, instead of turning off approval altogether.
1. Set the hours during which new trades may be opened. Exits are never blocked by that window.
1. Lower the risk percentage and the maximum number of open positions before you lower the number of human decisions.
1. Use Done for the day when you are stepping away. It blocks new entries and leaves every exit running.

Approve first remains the default and remains the right starting point for a beginner. Change it deliberately, in daylight, with small limits - not in the middle of a fast morning because you have just missed something.

SCREEN WALKTHROUGH

Short Term screen



Short Term contains copied positions and the current trade state from eligible signals.

What to look for

1. Open positions came from accepted live short-term signals or a subscriber action on this side.
2. Use Trim to reduce size and Close to exit your own position.
3. Sell everything, above the table, closes every open position at once.
4. A manual close affects your account; it does not close anyone else's trade.
5. Check Schwab after every manual action, especially if the response is delayed.
6. From version 0.16.0 this page can also ask you two questions. Both are covered in the next two chapters.

When Short Term asks you a question

From version 0.16.0 the Short Term page can ask you two kinds of question. Each appears as a coloured panel above your open positions, and neither one buys or sells anything by itself.

A position it does not recognise

The program compares your Schwab account against its own records every 30 seconds. If it finds a holding it did not open and cannot match to one of Andre's signals - shares you bought yourself, or a contract left over from something else - it will not invent a price, a size, or an exit for it. It asks you instead of guessing.

New buying is paused while it waits for your answer. Everything the program did open is still being looked after: stops, targets, and closing when Andre closes all keep running. Only opening something new is on hold.

Button	What it does to your money
Look after it	The program takes the position over. From then on it puts a protective stop on it, watches it, and sells it like anything else it bought. Choose this if the position came from one of Andre's trades.
Leave it alone	The program never touches it. It will not sell it, will not put a stop on it, and will stop asking. It stays yours to manage in the Schwab app. Choose this if you bought it yourself.

Either answer switches new buying back on straight away, and neither button sells anything. Anything you leave alone is then listed under **Positions you told us to leave alone**, so a mistaken answer does not become invisible.

An order Schwab never confirmed

If an order was sent but Schwab never confirmed whether it was accepted, the program stops and says so on every page. It will not try again, because trying again could buy or sell the same thing twice. Open your Schwab app, look at your positions, then come back and answer:

Button	When to press it
Ask Schwab	The program looks the order number up and believes whatever Schwab says. Try this first - it needs no judgement from you.
Yes, I own it	You have looked in the Schwab app and it is there. The program starts looking after it: stop, target, and selling when Andre sells. Nothing is bought by pressing this.
No, it never went through	You have looked and it is not there. The program writes it off and gives back the money it was holding aside. Nothing is sold by pressing this.

Until you answer, that position is stuck: nothing is watching it, the Close button refuses it, and it is holding on to part of what you set aside to trade with. Answer it the same day.

What each position status means

These words appear in the Status column on Short Term and under Why in the Closed table beneath it. They are written in plain English on purpose: an earlier version printed the program's own internal wording, or in the Closed table nothing at all.


What it says	What it means for you
Open	You hold it and the program is looking after it - protective stop, target, and closing when Andre closes.
Closed	The program sold it. The Closed table shows what you made or lost.
Closed in your Schwab app	You no longer hold it, and the program did not sell it - it disappeared from your Schwab account. Usually that means you sold it yourself, or Schwab closed it at expiry or by assignment. The program only says this after seeing it missing three separate times, and it records the result so your daily loss limit counts it.
Waiting for your decision	A holding the program cannot match to one of Andre's signals. New buying is paused until you press Look after it or Leave it alone.
You said this one is not yours	You pressed Leave it alone. The program will never buy, sell, or put a stop on it. It is still in your Schwab account and it is entirely yours to manage.
We could not confirm this	An order was sent and Schwab never confirmed the outcome. Check your Schwab app, then press Ask Schwab, Yes I own it, or No it never went through.
Never bought	The request was refused before an order was placed. Nothing left your account.
Being placed	The order is on its way to Schwab. Pressing anything again does not make it faster.
Expired before it was answered	A trade waited for your approval and the time ran out. Nothing was bought and nothing was lost - you simply did not take that trade.

A holding the program has been told is **not managed** is one it must never touch. Those are counted on the Alerts page under Holdings we could not match to a signal, so they stay visible instead of being quietly ignored. They do not use up your position limit and the program will not sell them, ever.

Schwab is always the final word. If a status here and your Schwab app disagree, believe Schwab. Protect the account first and troubleshoot second.

SCREEN WALKTHROUGH

Signal Types screen



Signal Types explains each strategy and lets the subscriber stop future entries from a strategy.

What to look for

1. Taking these means future eligible entries are allowed through your local filter.
2. Turn off stops new entries of that kind on this computer.
3. Turning off never blocks the exit for a copied position already open.
4. Open How this works before deciding whether to take a strategy.

The Alerts page

Alerts is a new page in the top menu, between Signal types and System map, with a count beside it when something is waiting. It is where the program writes down anything it needs to tell you, before it tries to show you a notification. That way a pop-up that never reached your screen - because the laptop was locked, or asleep, or busy - costs you the pop-up and not the fact.

Nothing here disappears on its own, and nothing here is lost when you close and reopen the program. The important ones stay in front of you until you press **I have read this**.

Is it running?

The program is several separate parts that can fail independently. Each is listed here with what you lose if it stops: listening for Andre's signals, opening new trades, closing your trades, checking your Schwab account, and housekeeping. Each shows Running, Waiting, Stuck, or Stopped.

Before this page existed, a broken program and a quiet market looked exactly the same from every screen. If a part that matters has stopped, a red banner appears on every page saying what is not happening. The fix is to close the program and start it again; if it happens twice, send Andre the log file.

Checking your Schwab account

This is the running score of the every-30-seconds comparison between what Schwab says you hold and what the program thinks you hold: how many checks have run, how many positions matched, how many were closed in your Schwab app rather than by the program, how many protective stops were confirmed, how many the program had to put back, and how many holdings it could not match to a signal.

Positions left with no stop should be zero. If it is not, open your Schwab app and look at that position yourself before doing anything else.

Signals from Andre

How the program is reading Andre's list, how many times it has checked, and the important line: how many signals arrived too late to trade. A trade discarded for being too old used to be indistinguishable from a quiet market.

If **Closes that arrived too late to act on** is not zero, a position may still be open here that Andre has already closed. Open Short Term and close anything you no longer want to hold.

Everything, newest first

The full list, each item marked Important, Worth knowing, or For your records. Read them, tick off the ones you have dealt with, and treat an empty page as the normal state - because it is.

Opening Range Breakout (Simple 2R)

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	options
Typical session	09:35 ET (earliest, once the range completes) → 11:00 ET cutoff

The idea in one sentence

The first 5 minutes of the session draw a box. Trade the first break out of that box, stop at the breakout candle's other end, target twice the risk.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: The range is the first 5 minutes of the day. Entry is the first break out of that box; the stop is the box's other end, and the target is twice that risk.

Setup — the opening range

At 09:30 ET the market reopens with the night's news priced in, and the first few minutes are the loudest, highest-volume auction of the day. The strategy takes the highest high and lowest low of those first 5 minutes and calls that the opening range. Nothing is traded while the range is forming; the range is simply two horizontal lines the rest of the morning is measured against.

Entry — the first break of either side

After the range closes, the engine watches the last price. The moment price trades above the range high it buys calls; the moment it trades below the range low it buys puts. It does not pick a side in advance and does not wait for a candle to close — the break itself is the trigger. Only the first break is taken; the strategy does not re-enter after being stopped.

Stop — the breakout candle's opposite extreme

The stop goes at the far end of the very candle that caused the break: its low on a long, its high on a short. The logic is that a genuine breakout should not trade back through the bar that produced it. This is a STATIC price — it is computed once at entry and never moves.

Target — a flat 2R

Risk (R) is the distance from entry to stop. The target sits two of those distances beyond entry. There is no scaling out and no runner: one entry, one stop, one target. A 33% hit rate breaks even; anything above that is profit.

Where it breaks down

Two failure modes dominate. First, the whipsaw open: price pokes above the range, fails, and reverses straight through the low — one loss on each side if re-entry were allowed, which is why it isn't. Second, the too-wide range: a violent first 5 minutes makes R enormous, so the 2R target sits somewhere price will not reach before midday. The range-width gates exist for exactly that second case.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

Andre ORB (no TP, -20% premium stop)

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	options
Typical session	09:30 ET open through a 10:30 ET cutoff on new entries; every position is closed out flat by the end of the day, never held overnight.

The idea in one sentence

Trades the exact same opening-range break as the plain ORB strategy -- same entry, same stop, same timing -- but nothing forces an exit at a fixed profit target. The position is left open to let a real trend run further, with only a wide loss stop and the close standing between it and the exit.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: The same range and the same break as the plain ORB strategy -- the entries are identical. There is no profit target at all, which is why none is drawn: the position is left to run. It ends in one of three ways -- the option loses about a fifth of what was paid, price closes back through its moving average twice in a row, or the clock runs out and everything is sold flat. The loss limit is a share of the premium rather than a level on the chart above, so it cannot be drawn there honestly.

Setup and entry -- identical to the plain ORB strategy

The opening range and the break that triggers a trade are drawn from the exact same rules as the plain ORB strategy: the first few minutes of the session mark a high and a low, and the first clean break of either side is bought. Nothing about how or when a trade opens is different here -- the two strategies enter at the same moment, in the same names, on the same signal.

Stop -- a wide, fixed loss limit

The stop is not the breakout candle's opposite edge the way the plain version uses. Instead the option position is closed once it loses about a fifth of what was paid for it. That is a wider leash than a typical scalp stop, deliberately, so that ordinary give-back on a real trend does not knock the trade out before it has a chance to work.

No profit target -- this is the whole point

There is no take-profit level anywhere in this strategy. A typical scalp locks in a double of its risk and moves on; this version does not, because the profitable trades in this family tend to keep running well past a small fixed target, and capping them early was found to give back more than it protected. The tradeoff is real: more of the small losing trades run their full loss, in exchange for the winners being allowed to pay for them.

Exit -- stopped out, or flattened at the close

Only two things end a trade: hitting the wide loss stop, or the trading day ending. Every position still open in the afternoon is sold flat before the close -- nothing from this strategy is ever carried overnight, regardless of whether it is winning or losing at that point.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

Opening Range Breakout (5m RVOL, Legacy)

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	options
Typical session	09:35 ET (the first 5-minute bar after the range) → 11:00 ET cutoff, 90 minutes after the open

The idea in one sentence

Rank the whole watchlist by how heavy its first five minutes were, keep the eight busiest, and trade the first 5-minute bar that CLOSES outside the opening range — then hold the runner, because the target is set where it will never be reached.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: Same shape, but only on the busiest names of the morning, and only on a 5-minute bar that CLOSES outside the range rather than just touching it.

Setup — one candle is the whole range

This engine works on 5-minute bars and its opening range is five minutes long, which means the range is a single bar: the 09:30–09:35 candle. Its high and its low are the only two levels the strategy cares about. There is no averaging, no second confirmation bar, and no separate range-building period — by 09:35 the setup is fully defined and the state machine starts looking for a trigger on the very next bar.

Entry — the bar has to close beyond the level

This was not a theoretical preference — it was added on 2026-08-03 after a USO short entered on a 0.13 wick below the range low that closed 0.27 back inside and lost. Both sides are live: unlike the original research spec, which used the opening candle's colour to pick one tradable side per day, this engine ships with direction set to 'either', so it scans long first and then short, and the doji skip never applies.

Stop — the other side of the range

The stop is the opposite edge of the opening range, padded by 0.05% so a one-tick brush of the level does not close the trade: the range low times 0.9995 on a long, the range high times 1.0005 on a short. That is a STATIC price fixed at entry.

Target — a number chosen so it is never hit

The target multiple is 10R. On a typical opening range that puts it more than ten percent away on the underlying, which is not a forecast — it is a way of saying 'no target'. The engine's own signal text spells this out, printing 'exit: 10R target' where every other strategy prints a real level. The stated thesis is that the runner is the edge: you accept many small stop-outs at the range edge in exchange for the occasional day that trends from 09:40 to the close. What actually closes these trades in live trading is therefore the premium take-profit, the 15-minute structure trail, or the end-of-day flat — not the target.

Where it breaks down

The obvious one is the range that is simply too wide. A violent opening bar puts the stop the full width of that bar away, and because the stop is a percentage of the underlying converted to a premium stop, the trade can be risking a fifth of the position on noise. There is no range-width filter in this engine — only a floor saying the range must be at least 0.1% of price, which rejects nothing on a real open. The second is the top-eight ranking itself: RVOL is measured on the opening bar only, so a symbol that gapped on news and then went completely dead still ranks top of the list all morning. The third is the 10R target's arithmetic tail — a strategy whose winners come from a handful of trend days has a long, expensive stretch of stop-outs between them, and the engine offers no scale-out to soften that.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

ORB v2 (Break-Confirm-Retest)

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	shares
Typical session	09:45 ET (earliest — the 15-minute range must complete) → 15:30 ET last entry → 15:55 ET blanket scalp flat

The idea in one sentence

The opening range is treated as a level, not a direction. Two whole candles have to close clear of it, then price has to come back, touch it and get rejected, and only then does a break of that rejection candle put you in — riding a 13-period EMA until a candle closes through it.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: The break alone is not enough: price has to come back, touch the range again, get rejected, and only then does a break of that rejection candle put the trade on.

Setup — the opening range is a level, not a bias

The first fifteen minutes of the session — three 5-minute bars by default — produce a high and a low, and those two prices are all this strategy takes from the open. It deliberately does not read the opening candle's body or colour to pick a side, which is the single thing Andre changed when he redesigned the engine on 2026-07-31: the old behaviour let one indecisive first candle commit the day to a direction. Here both sides stay armed, and the market chooses by what it does to the level. The high and the low are full wick extremes, so a spike that nobody traded at still counts as part of the range.

Confirmation — two candles entirely clear of the level

A break is not the trigger. The engine replays every completed post-range bar of the day and counts consecutive candles that sit ENTIRELY on the far side of the level — the low of a bull candle above the range high, wick included, not merely its close. Two of those in a row arm that side. The counter resets to zero the moment one candle fails the test, so a single stretch of two clean bars is required rather than two clean bars scattered across the morning. The point of insisting on wicks is that a candle whose lower shadow is still inside the range is a candle where sellers were still active at the level, and the whole thesis is that they are not.

Entry — continuation through the rejection candle

The trade is taken when price takes out the rejection candle's extreme in the direction of the break: its high for a long, its low for a short. The live batch quote is what tests that, so the fill is not pinned to a bar close. Two things can still refuse it. If the completed bars show the trigger was taken out on some earlier bar rather than the most recent one, the move was missed and the engine will not chase it — that side simply dies. And if the live quote is already more than half an opening-range height past the trigger, the entry is declined as late discovery, because the stop does not move to accommodate a worse fill and the risk would quietly inflate.

Stop — a quarter of the range inside the level (STATIC)

The stop sits a quarter of the opening range's height back INSIDE the level: range high minus 0.25 × range height for a long. It is computed once at signal time, written onto the position, and never moved. It is checked intrabar against the live share price on every monitor tick, so it is a real stop rather than a close-based one. This is deliberately tight — the original backtest note records that swapping it for the opposite side of the range collapsed the result from +0.068R per trade to +0.019R, so the tight stop is load-bearing rather than incidental. It also means the number of trades that die on noise is high by design, and the strategy pays for that with the open-ended exit below.

Where it breaks down

The stop sits inside the range, so any retest that overshoots slightly deeper than the rejection candle takes it out — and this pattern's whole premise is that price comes back to the level, so it is being deliberately invited into the zone where the stop lives. That shows up in the recorded numbers as a 40% win rate. The edge is small and entirely dependent on the EMA-follow producing a few large winners; the same note records a median trade of 0.69% of price, which means commissions and spread eat the result on anything but liquid names. Finally, the whole day's arming state is recomputed from scratch on every scan rather than persisted, so it is honest about restarts but also means the engine needs the 09:30 bar to exist — if the opening bar is missing from the feed, it refuses to form a range at all and the symbol is skipped for the day.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

Andre's Ladder

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	shares
Typical session	09:30 → 16:00 ET; 15:55 ET blanket scalp flat

The idea in one sentence

Find a clean impulse leg on 5-minute structure, then buy it back almost the whole way down — a 95% retracement — with a stop just beyond the leg's origin, and manage the exit up a ladder that moves to break-even at the halfway mark and locks in at three-quarters.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: A clean impulse leg, then a retrace of almost the whole move -- about 95% -- and the buy-back, with the stop just beyond where the leg began.

Setup — a higher low, then an impulse, then a deep retrace

The engine looks for the freshest pivot high on 5-minute structure that is preceded by a higher low. The pivot high is the EXTREME; the higher low before it is the ANCHOR; the distance between them is the LEG, and every level in the trade is a fraction of that one measurement. The 'higher' part matters — the low before the impulse has to sit above the low before that, which is what makes the structure a sequence rather than a single bounce. Pivots are read on candle BODIES rather than wicks by default, on the reasoning that the solid part of a candle is where price was accepted and the shadows are auction noise. Shorts are the exact mirror: a pivot low preceded by a lower high.

Entry — 95% of the leg given back

The trade is not taken on the impulse. It is taken when price comes back and gives up almost all of it — the shipped default is 98% of the leg, the live setting is 95%, which puts the entry within a few cents of the anchor. That is a deliberately extreme retracement, and it is what makes the risk so small: you are buying a few cents above the level that invalidates the whole idea. It also makes the strategy counter-trend by construction. The trigger is the live batch quote, not a bar close — a 98% retrace is a touch-and-go that a stale close misses.

Two stops, and they are different animals

The LADDER stop sits at the 105%-of-leg level — 5% of the leg beyond the anchor — and it is CLOSE-based: a wick through it holds, only a completed 5-minute close beyond it exits. That is the validated behaviour and it is what lets the trade survive the spike that usually accompanies a genuine reversal. The HARD stop is different: it is an intrabar level at twice the entry-to-ladder-stop distance, checked against the live share price on every monitor tick, and it never moves. It exists because the study measured single fills reaching –62R when only a close-based stop was in play; adding the intrabar –2R stop cut maximum drawdown from about $26,900 to $10,400 while ADDING profit. The hard stop is also the denominator of the position size, so the dollar loss it represents is fixed per trade by design.

The ladder — break-even, then a ratchet (DYNAMIC)

Once in, the trade climbs a three-rung ladder measured against the same leg. Reclaim half the leg and the stop moves up to break-even. Reclaim three-quarters and it ratchets again to sit at the halfway level, which locks in a real gain. Full reclaim of the extreme is the take profit. The rungs ADVANCE on an intrabar touch — the monitor polls several times a bar, and only bars that overlap or follow the entry may count — while the stop itself still only fires on a completed close beyond whichever rung is current. So the ladder tightens quickly and releases slowly, which is why it is drawn as a stepped line rather than a flat level. It ratchets in one direction only; a stage never regresses, and if the bot restarts the stage re-derives from the bottom rung, which can only ever make the stop looser.

Where it breaks down

The entry sits a few cents above the price that invalidates it, so the strategy's whole character is a high hit rate punctuated by a stop that is trivially easy to reach. On the raw study the 5-minute ladder produced very large gross profit alongside a $26,900 drawdown and a single –62R fill; the hard stop is what makes the shape survivable, not what makes it profitable. Because it is counter-trend by construction it fights every trend filter in the system, and it currently runs WITH the AI-confirm veto and the sector-rotation filter in the loop — both of which the 2026-07-30 studies measured as cutting ladder profit by 40–45%, and neither of which was present in any validation run. The take profit is a full reclaim of the extreme, which is a long way from a 95% retrace entry, so the trade needs the leg to repeat itself almost exactly. And the stage state that drives the ladder lives only in memory on the position object, so a restart mid-trade silently gives back a break-even or a locked-in ratchet.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

EMA/VWAP Cross 3min

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	both
Typical session	09:30 → 16:00 ET; 15:55 ET blanket scalp flat

The idea in one sentence

Let the 9EMA and session VWAP agree on a direction, wait for price to dip back and tag VWAP, and enter on the first 3-minute candle that closes back through the 9EMA — then hold until a candle closes back through it the other way.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: The line is the 9EMA with session VWAP agreeing. Entry is the first 3-minute candle that closes back through the 9EMA; the trade is held until one closes back through it the other way.

Regime — the standing relationship, not one candle

Before anything else the engine asks a single question: is the 9-period EMA of 3-minute closes standing above session VWAP, or below it? Above by more than a tolerance band means longs only; below by more than the band means shorts only; anything in between is neutral and nothing trades in either direction. This is a hard gate — a long can never fire while the EMA is under VWAP. It reads that way because of a real bug Andre chart-annotated on 2026-08-04: the old test was one completed candle's CLOSE against both lines, and a bar closing above VWAP is automatically also above the EMA whenever the EMA sits below VWAP, so a single spike could flip the read bullish for one tick while the actual standing trend never left the bearish side. The fix was to ask about the two lines, not about a candle.

Setup — the sweep arms, it does not enter

Inside a live regime the engine watches for price to come back and tag VWAP: the live quote within a tolerance of VWAP while the last completed candle's close was still on the trend side. That is the wick through fair value the original spec was about — buying the dip into VWAP inside an uptrend. It used to be the entry. It is now only an arm, recorded per symbol with the bar index it happened on, so confirmation can only ever be judged on a candle strictly after the sweep was seen. Any change of regime — including a drift into neutral — wipes the arm.

Entry — the reclaim of the 9EMA

The trade fires on the FIRST completed 3-minute candle after the arm whose close is back on the trend side of the 9EMA. That is the extra confirmation Andre asked for on 2026-08-04: a sweep alone proves price visited fair value, a reclaim proves it was rejected there. If no candle reclaims within the arm window the setup expires unfired rather than lingering. One further gate is applied last, after regime, setup and entry have all confirmed: price must be outside the opening range. Inside the range the entry is refused but the arm is deliberately NOT reset, so the same setup can still fire later once price leaves the chop zone.

Exit — the 9EMA the other way (DYNAMIC)

There is no take-profit. The position is held until the first completed 3-minute candle CLOSES through the 9EMA against the trade. A wick through the EMA is a sweep and holds; a close through it is a break and exits. Because the EMA moves with price, the effective exit level rises through a winning long and falls through a winning short — this is a genuinely dynamic line and the reason the schematic draws it as a curve rather than a flat level. Candles that completed before the fill can never trigger it, which is what stops the setup's own price action closing the trade it just opened. When the data is too thin to judge, the exit check returns nothing and the position is held — a missing read is never treated as an exit.

Where it breaks down

The reclaim confirmation costs you the best fills: by the time a candle has closed back through the 9EMA, price is usually well off the sweep low, so the entry is worse than the sweep and the fixed-percentage stop is measured from that worse price. In a genuinely choppy session the pattern repeats endlessly — sweep, reclaim, close back through — and the engine will take each one, because nothing limits entries per symbol per day. The neutral band is the main defence against that and it is also the main source of missed trades. And the strategy's whole geometry assumes VWAP is a real level; on a name whose volume profile is lumpy, or early in the session when few prints have accumulated, VWAP moves enough that a sweep is an artefact of the calculation rather than an event in the market.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

SMC (Sweep -> MSS -> FVG Retrace)

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	shares
Typical session	Regular hours only, 5-minute bars. Nothing can fire before roughly 10:10 ET, no fresh entries after 15:30 ET, and anything still open is swept flat at 15:55 ET — this book never holds overnight.

The idea in one sentence

A pool of resting stops gets wicked and rejected, structure then breaks the other way with a gap in the impulse, and you buy the pullback into that gap. Stop at the wick, target the next pool.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: A pool of resting stops gets swept, structure breaks the other way leaving a gap, and the trade buys the pullback into that gap. Stop at the wick, target the next pool.

Beat one — the pools, and the sweep

Before it can look for anything the engine draws its pools: the prior regular-hours high and low, plus every confirmed swing high and swing low from yesterday and today, where 'confirmed' means the pivot has six bars on each side that did not exceed it. A sweep is one completed 5-minute bar whose high pushes through a high pool while its close comes back below it, or whose low pushes through a low pool while its close comes back above. The wick is the sweep and the close is the verdict. From that moment on, any completed close beyond the pool kills the setup outright — that is a real breakout, not a stop hunt, and the engine wants no part of it.

Beat two — the market-structure shift, certified by a gap

A wick proves stops were taken. It does not prove anyone changed their mind. So within the next twelve bars the engine demands a completed close through the most recent confirmed internal swing on the opposite side — internal swings use a much tighter two-bar pivot than the pools do, so this is a fine-grained structural level, not another major one. That close is the market-structure shift. On top of it, the run from the sweep bar to the shift bar must contain a fair value gap: three consecutive bars where the first bar's high sits below the third bar's low, leaving a price band nobody traded. That untraded band is the evidence that the move was displacement rather than drift. No gap, no trade.

Beat three — the retrace into the gap is the entry

The engine does not buy the structure break. Backtesting entry-at-the-shift was negative in all twelve parameter cells tried, which is why the third beat exists. Instead it waits up to twenty-four bars for price to come back into the fair value gap and triggers the moment the live quote reaches the near edge of that gap — the top edge on a long, the bottom edge on a short. Filling deeper inside the gap is simply a better price. One further filter applies: the gap must sit in the discount half of the range carved out between the sweep and the shift for a long, the premium half for a short. Buying the top of your own impulse is not the trade; buying the part of it the market has marked down is.

Stop and target

The stop is the sweep wick itself — the exact extreme of the bar that hunted the pool. It is a fixed price, set once at entry and never moved, and it is enforced two ways: against the live quote on every monitor tick as the position's hard level, and again as a completed close through it. The target is the nearest liquidity pool on the other side that sits at least one R away. If no such pool exists the trade is simply not taken — there is nothing drawing price in your direction, so there is no reason to expect it to travel. That rule means the reward side is market structure rather than a fixed multiple, and R multiples on real signals vary widely.

Where it breaks down

Three ways, and they are all visible in the numbers. First, the chain is long — pool, sweep, shift, gap, retrace, all inside fixed bar windows — so most days most symbols produce nothing, and the one-trade-per-symbol-per-day lock means a good setup later in the day is lost if a mediocre one fired at 10:30. Second, the honest edge is thin and tail-driven: the shipped backtest is 45.2% wins at +0.170R per trade over 312 trades, with the top ten winners carrying most of the sum, so a month can easily look flat or negative without anything being wrong. Third, the in-memory bracket. The target is gone until re-entry.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

SMC 15m (Sweep -> MSS -> FVG Retrace)

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	shares
Typical session	Regular hours only, on 15-minute bars. The earliest possible signal is about 11:30 ET; the scan stops at 15:30 ET and anything open is flat by the 15:55 ET sweep, which leaves roughly a four-hour window in which this strategy can act at all.

The idea in one sentence

Exactly the same sweep → structure-shift → gap-retrace trade as the 5-minute SMC strategy, run on 15-minute bars. Far fewer signals, each about three times larger, and a hold measured in hours rather than minutes.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: Exactly the same sweep, break and retrace, measured on 15-minute bars instead of 5 -- far fewer signals, each about three times larger, held for hours.

Be clear about what this is

The setup, the trigger, the stop rule, the target rule and the kill conditions are byte-for-byte the ones documented on the the 5-minute SMC strategy card. What this card is for is the part that genuinely differs — what changes when the same rules are applied to bars three times the size, and why Andre would run this instead of, or alongside, the 5-minute book.

The windows scale with the bars, and they scale hard

Reusing the 5-minute numbers on 15-minute bars would have meant a three-hour sweep window and a six-hour entry window, which is longer than the session. So a second defaults dict, DEF15, replaces four of them whenever the 15-minute timeframe is in force: the pool pivot half-width drops from six bars to two, the internal pivot from two to one, the sweep-to-shift window from twelve bars to six and the shift-to-entry window from twenty-four to twelve. In wall-clock terms that is a ninety-minute window to break structure and three hours to retrace — wider than the 5-minute book in time, tighter in bars. Note also that a two-bar pool pivot on 15-minute bars is a coarser object than a six-bar pivot on 5-minute bars, so the pools themselves are different levels, not the same levels seen through a longer lens.

What the bigger bars do to the trade

Everything about the trade's geometry inflates together. The fair value gaps are wider bands, so the retrace entry is a looser touch. And the hold stretches: a trade that resolves in half an hour on 5-minute bars can occupy most of an afternoon here. The measured version of all that is n=75 over the same 90-symbol three-month window against n=312 for the 5-minute book — roughly a fifth of the trades — at +0.40 to +0.50R each against +0.170R.

Why run both

Because they rarely fire on the same thing. Only about twelve percent of symbol-days overlap between the two books, which is what makes running them concurrently a diversification rather than a doubling-down; that overlap figure is the reason the two were split into separate roster strategies in the first place. The 15-minute book also measured a much better profit-to-drawdown shape — 7.4× against 2.2× — but on seventy-five trades, which is not many. Treat the per-trade numbers as a small sample and let paper data accumulate before sizing on them.

Where it breaks down

The late start is the first problem and it is structural. Needing eight completed 15-minute bars means the engine is blind until about 11:30, and the sweep-to-shift-to-retrace chain then needs several more bars, so in practice this book is an afternoon strategy with a 15:30 cutoff bearing down on it. Setups that would have completed at 15:45 simply expire. The third is sample size — seventy-five trades is enough to be encouraging and nowhere near enough to be confident, and the four retuned window values were chosen on that same small sample.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

SMC Swing 1H (Sweep -> MSS -> FVG, multi-day)

Quick fact	What the app says
Usual horizon	swing
Usual instrument	shares
Typical session	Scans during regular hours only — no entry before 09:35 or after 15:45 ET — but the position is a swing and is held overnight. A trade is expected to live about five trading days.

The idea in one sentence

The same sweep → structure-shift → gap-retrace idea as the 5-minute SMC strategy, but on 1-hour bars with pools three weeks deep and a hold measured in days. The only overnight strategy in the SMC family.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: The same idea again on 1-hour bars, with pools weeks deep and a hold measured in days. The only setup here that stays on overnight.

The same three beats, at a completely different scale

Structurally this is the exact-ICT chain: a liquidity pool is wicked and rejected, structure then breaks the other way with a fair value gap in the impulse, and the entry is the retrace back into that gap. What makes it a different strategy rather than a different setting is the scale of every object in it. The pools are 1-hour swing pivots that stay live for a hundred bars — about three weeks of trading — rather than today's and yesterday's 5-minute pivots. The sweep is a full hour of trading that pushed through a level and closed back inside it. The structure shift has eight hours to arrive, the retrace sixteen. And the trade then sits through nights, weekends and whatever the tape does at the next open.

What holding overnight actually does to the risk

This is the part that separates this card from the other three, and it deserves to be plain. A stop is a price, and between 16:00 and 09:30 there is no price you can trade at. The stop sits at the sweep wick and is enforced against the live quote, so if a symbol gaps through it overnight the position exits on the first tick of the next session — at whatever that tick is, not at the stop. Your loss on a gap day is not one R; it is however far the gap went. The two-year study modelled exactly this, filling gaps at the open rather than at the stop, so the published +0.296R per trade already carries that cost; what it cannot carry is the tail — an earnings print, a guidance cut, a sector shock. This engine has no earnings filter of its own. The second overnight cost is opportunity: capital is committed for days at a time, and the calendar timeout will close a trade that has gone nowhere whether or not the thesis has actually been disproved.

Stop, target and the clock

Three exits, in the order they are checked. First the calendar timeout: once the position is its hold limit old it is closed regardless of price — that is roughly five trading days at the default of seven calendar days. Then the target, the nearest opposite 1-hour pool at least a minimum reward-to-risk away, taken on a completed-bar touch. Then the stop, at the sweep wick, enforced both as an intrabar level against the live quote and as a completed 1-hour close through it. The stop is static: it is set at entry and it never moves, in either direction. There is no trailing stop, no breakeven ratchet that can realistically arm, and no partial scale-out.

Where it breaks down

Four honest problems. The overnight gap is the obvious one and is discussed above. The second is parameter fragility: the shipped k3/1 with 8/16 windows was the best in-sample cell of a grid, a neighbouring cell was also strong, and a nearby one was weak — the surface is not flat, so the in-sample choice is doing real work. The third is regime: every full half-year of the two-year study was positive and the single losing stretch is July 2026, which is the regime we are currently in, so a soft start should be expected rather than treated as evidence of a break. The fourth is quieter — the pool history is bounded by the shared structure feed, which reaches back about fifteen calendar days, or roughly seventy-five 1-hour bars. The hundred-bar pool age cap is therefore never the binding constraint live, and the live map is shallower than the backtest's was.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

Liquidity Flow (sweep vs acceptance)

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	shares
Typical session	Regular-hours 5-minute bars, entries only between 09:45 and 15:30 ET. Anything still open is closed by the 15:55 ET end-of-day sweep.

The idea in one sentence

Map every liquidity level on the chart, score them, and wait for price to interact with a good one. If liquidity was TAKEN and price reversed, fade it; if liquidity was CONSUMED and price kept going, follow it. Target the next zone on the map.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: Every liquidity level is scored first. If liquidity was TAKEN and price reversed, fade it; if it was CONSUMED and price kept going, follow it.

The question this engine is built around

Every other level-based strategy in the roster asks where the levels are. This one asks a different question, and the whole design falls out of it: was the liquidity at that level taken so price could reverse, or consumed so price could continue? Those two things look almost identical for the first minute and mean opposite things. A sweep is a shallow poke that closes back inside — somebody filled against the stops and let price go. Acceptance is a drive through that keeps closing beyond — the level genuinely broke and the market is trading above it now. Sweep says fade; acceptance says follow.

Step three — which zones are worth entering on

Here the engine does something none of the other strategies do: it distrusts its own weights. That table found the hand-set weights close to inverted: the best-performing type, the low-volume node, carried the lowest base weight, while equal highs and lows carried one of the highest and measured near zero. So entries are gated on the measured table rather than the weights. A type with a positive measured edge is a 'fade' type, a negative one is a 'follow' type, anything in between or under-sampled is not enterable. Nothing is deleted — every zone still counts for confluence and still qualifies as a target. What is blocked is entering on it. If the table file is missing the gate fails closed and nothing trades.

Step four — classify the interaction

Shallow poke, closed back inside within a few bars, still inside now: that is a sweep, and the trade is the fade. Deep drive, two or more closes beyond, none back inside: that is acceptance, and the trade is the continuation. A close-location delta proxy runs alongside as a tiebreaker and flags the 'trapped' case, where flow pushed in the pierce direction and produced no progress. Be clear about what that proxy is: it is close position within the bar's range weighted by volume, and it cannot tell a buyer lifting the offer from a seller hitting the bid. It is not order flow, and the module says so at the top.

Stop, target and the travel budget

On a sweep the stop goes a tenth of an ATR beyond the sweep extreme; on an acceptance it goes a quarter of an ATR back inside the level that broke. Either way it is a fixed price set at entry. Any setup whose risk exceeds two percent of the share price is discarded outright. That combination has a consequence worth internalising: a crowded map above your entry can kill an otherwise perfect setup, because the nearest zone is too close to clear 1.5R. One more subtlety on the confirmed path: because entry now happens up to twelve bars after the interaction, the ordinary distance gate would reject everything — measured, distance at the shift bar runs from 1.6 to nearly 7 ATR against a 1.5 gate, and the branch fired exactly zero times.

Where it breaks down

Start with the honest scope: the only historical market data this repo has is OHLCV bars. There is no stored tape, no Level II depth and no options-chain history, so true delta, absorption, iceberg detection, replenishment, gamma walls and dealer positioning are all absent — the spec this engine implements describes them and the code implements the structural core without them. What is left leans on a delta proxy that is a weak stand-in. Then there is the narrowness of the shipped configuration. Both are on the sell side of the map, which means that as configured today this engine can only produce LONGS. Both also carry base weights below the forty-point score gate, so they only become tradable when confluence lifts them over it. That is a very small target, and it is the most likely reason this engine can scan all day and report nothing.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

VWAP Trend Pullback

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	options
Typical session	Regular hours only, 09:30–16:00 ET. Nothing before roughly 11:30 ET. No cutoff of its own — it will keep signalling into the close.

The idea in one sentence

Price has spent most of the last two hours on one side of session VWAP. Wait for it to rotate back to VWAP, then buy the resumption when it takes out the high it made on the way back up.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: The line is session VWAP. Price has spent hours on one side of it; the trade waits for a rotation back to it and buys the resumption.

Setup — a trend measured against VWAP, not against a moving average

Session VWAP is the volume-weighted average price everyone who traded today actually paid. When price holds above it hour after hour, buyers are systematically paying up and the average participant is offside short.

Setup — the pullback has to actually reach VWAP

That swing low only counts if the bar that made it closed at or below VWAP times 1.001 — in other words the dip has to have come all the way back to the average price, not merely paused a few cents off the highs. That single test is what makes this a pullback strategy rather than a breakout one: you are buying the trend where it is cheap relative to the day's own mean, and the stop sits at a structure low rather than at an arbitrary distance.

Entry — the resumption takes out the recovery high

Once the pullback low is confirmed the engine watches the highest high made from that swing-low bar forward. The trigger is the current price trading above that running high: the dip is over, the sellers who pressed into VWAP have been absorbed, and the trend leg is starting again. The mirror image applies to a downtrend, where the pullback is a rally into VWAP and the trigger is a break of the lowest low made since the swing high. There is no candle close requirement and no re-entry logic; the engine simply re-evaluates on every scan and stops finding the setup once price has moved on.

Stop and targets — one static level and two branches

The stop is the pullback swing extreme itself: the swing low on a long, the swing high on a short. It is computed once, at signal time, and never moves — no trailing, no ratchet, no break-even step. Risk (R) is the distance from entry to that level. The target has two branches. Only when the prior extreme has already been exceeded does the engine fall back to a flat entry ± 2R.

Where it breaks down

Three ways, and the first is severe. The literal trigger compares the current price against the maximum high of a window that includes the bar being evaluated, so whenever the price handed in is a bar close — which is every bar of every backtest replay, and every live scan where the batch quote came back empty — the comparison is arithmetically impossible and the engine returns nothing. Second, even when it does fire, the trend test is a count of closes and says nothing about slope: a symbol that ground sideways two cents above VWAP for two hours reads as a 100% uptrend, and the ADX and VWAP-slope gates exist precisely to catch that case but are off by default. Third, buying a pullback into VWAP is the same trade as fading a trend change until it isn't; on the day the trend genuinely ends, the pullback that looks best is the one that keeps going, and the stop at the swing low is exactly where everyone else's is.


Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

VWAP Mean Reversion

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	options
Typical session	Regular hours only, 09:30–16:00 ET. The earliest possible signal is about 10:10 ET. It defines no cutoff of its own.

The idea in one sentence

Price has stretched a long way from session VWAP and has stopped going. Fade it — short the failure back toward VWAP with the stop beyond the excursion extreme and VWAP itself as the target.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: Price has stretched a long way from VWAP and stopped going. The trade fades it back toward the average, with the stop beyond the extreme.

Setup — a rubber band, measured in percent

Session VWAP is where the average share traded today changed hands, and intraday price tends to orbit it. Everything about the setup — how extended it is, where the stop goes, what the trigger level is — comes out of that one short window, which is both what makes the engine simple and what makes it self-referential.

Entry — the excursion has to fail, not just pause

Being far from VWAP is not a reason to trade; being far from VWAP and turning is. On a short the engine waits for price to trade back below the reaction low of that lookback window while still being above VWAP, which is the point where the last buyers who chased the high are underwater and the move has visibly broken. On a long it is the mirror: price reclaims the reaction high of the window while still below VWAP. The 'still on the same side of VWAP' condition matters — once price has already crossed back, the reversion the strategy exists to capture has happened without you and the trade is refused.

Stop and target — a fixed level and a snapshot of VWAP

The stop is the excursion extreme: the highest high of the lookback window on a short, the lowest low on a long. It is a single static price fixed at signal time — no trail, no break-even ratchet, no time-based tightening. The target is session VWAP itself, snapshotted at the moment of the signal, which makes it static too even though VWAP keeps moving afterwards. Be honest with yourself about the resulting geometry: because the stop is the far side of the same window whose near side you entered through, the risk is at least the whole width of that window, while the reward is only whatever is left between entry and VWAP. Reward below one R is the normal case here, not the exception, which means this strategy has to win often to be worth running.

Where it breaks down

First and most seriously, the literal trigger cannot fire from a bar close. Second, mean reversion is the strategy that works every day until the day it doesn't: on a genuine trend day the extension keeps extending, and because the stop sits at the excursion extreme it is exactly where a trending market goes next. The ADX, slope and realized-volatility gates are the intended defence and they are off by default. Third, even a correct fade can pay badly, because VWAP is rising into a short and falling into a long — the target moves toward you, but so does the reason the trade existed, and a snapshotted target taken at signal time can be stale by the time price gets there.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

Liquidity Sweep and Reclaim

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	options
Typical session	Regular hours only, on 5-minute bars. The earliest possible signal is roughly 10:40 ET. It has no entry cutoff of its own — it will keep scanning to the close.

The idea in one sentence

A level that has held for a while gets poked through, the poke fails, and price closes back on the original side. Trade the reclaim, stop beyond the failed poke, target the next level on the other side.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: A level that held for a while gets poked through, the poke fails, and price closes back on the original side. The stop sits beyond the failed poke.

Setup — a level worth hunting

Stops cluster under obvious lows and over obvious highs. The more times a level has been respected, the more resting orders sit just beyond it, and the more attractive it becomes for someone to push price through it and take that liquidity. This engine builds its shortlist of such levels from two places: the confirmed swing pivots of today's 5-minute bars, and yesterday's regular-hours high and low. It keeps the three most recent swing lows plus the prior-day low as candidate supports, and the three most recent swing highs plus the prior-day high as candidate resistances. The swing pivots are deliberately computed from bars that end before the sweep window, so the level being swept is never the sweep itself.

Trigger — pierce, fail, come back

Over the last few bars the engine takes the lowest low and the highest high. For a long it wants two things at once: that recent low must sit below a candidate support, and the current price must sit above it. That is the whole test — the level was traded through, and price is now back on the correct side of it. The short is the exact mirror: the recent high pushed above a candidate resistance and price has fallen back below. The current price is the live quote from the batch snapshot, not a bar close, so the reclaim is judged the moment the engine looks rather than at the end of a five-minute candle.

Stop — beyond the failed poke

The stop is the sweep extreme itself: the lowest low of the sweep window on a long, the highest high on a short. The reasoning is direct. The whole thesis is that the move through the level was a liquidity grab that failed; if price returns to that extreme, the grab was not a failure after all and there is nothing left to be long of. This price is computed once at signal time and never moves.

Target — the next pool of liquidity, else 2R

The target is the nearest candidate level on the opposite side of entry — the closest swing high or prior-day high above a long, the closest swing low or prior-day low below a short. The idea is that the sweep flushed one side of the book and price will now travel to the next place resting orders are stacked. Only when no such level exists ahead of entry does the engine fall back to a flat two-times-risk target. Nothing checks that the opposing level is far enough away to be worth the risk being taken.

Where it breaks down

The most common failure is that the sweep was not a sweep. Price traded below a swing low and came back — that also describes an ordinary pullback in a downtrend, and with the gate layer off there is nothing separating the two. The second failure is geometric: the target is the nearest opposing level, and the engine never checks that it is further away than the stop, so a swing high sitting a few cents above entry produces a trade risking the full sweep depth to make almost nothing. The third is chase. Entry is the live quote with no cap on how far past the reclaimed level it may be, while the stop stays pinned at the sweep extreme, so a fast reclaim inflates risk without moving the target. And the fourth is simply that a real break looks identical to a failed one until it doesn't: on trend days the level gets taken, price reclaims for one bar, and then goes right back through.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

Intraday Compression Breakout

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	options
Typical session	Regular hours only, on 5-minute bars. The earliest possible signal is roughly 10:35 ET. It has no entry cutoff of its own — it will keep scanning to the close.

The idea in one sentence

When a stock stops moving, the range it stops moving in becomes a box. Trade the first break out of that box, stop at the breakout candle's other end, target one full box height.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: The range here is a volatility squeeze -- the stock stops moving. The stop is the far side of the box and the target is one full box height.

Setup — a box, defined by tightness rather than shape

Volatility clusters. A stretch of quiet is usually followed by a stretch of movement, and the quiet stretch leaves behind an obvious set of edges that everyone can see. This engine looks at a fixed number of trailing 5-minute bars — twelve by default, an hour of tape — and takes their highest high and lowest low. If that range is narrow enough relative to its own midpoint, it is a box; if it is not, there is no setup and the symbol is dropped. That is the entire definition.

Entry — the first trade outside the edges

The box is computed from bars ending one bar before the present, so the most recent bar is a candidate breakout candle rather than part of the box it is breaking. The engine then compares the live quote to the two edges: above the box high it buys calls, below the box low it buys puts. It does not pick a side in advance and it does not wait for a bar to close — the quote being outside the box is the trigger. In the shipped configuration there is no buffer, so a single tick past the edge counts.

Stop — the breakout candle's other end

The stop is the low of the current bar on a long and its high on a short, provided that price is on the correct side of it; otherwise it falls back to the far edge of the box. The thesis is that a genuine expansion out of compression should not trade back through the bar that produced it. This is a static price, fixed at signal time. Be aware that the source contains a line intending to also cap the stop at the box midpoint, and that line is immediately overwritten and never takes effect — so in practice the stop can sit anywhere the breakout bar's low happens to be, including well below the box.

Target — one box height, with a 2R floor

The classic measured move: whatever the box was tall, project that same distance from the entry. It is a modest, defensible target — you are claiming the energy stored during the quiet period is worth about one range, not a trend day. Because a tight box can easily be shorter than the distance to the stop, the engine checks: if the box-height target would not even clear one times risk, it is replaced with a flat two-times-risk target instead. So the trade is never knowingly taken at worse than 1R, and on the very tightest boxes it quietly becomes a 2R trade.

Where it breaks down

The false break is the whole risk, and it is common — a box is a magnet for stop orders sitting just beyond both edges, so poking one side and reversing is a profitable game for someone else. With the gate layer off, nothing distinguishes a one-tick graze on falling volume from a genuine expansion; the buffer and volume gates exist for precisely that, and they are off. The second problem is that the tightest boxes are the most attractive on paper and the worst in practice: the narrower the box, the more often the box-height target collapses into the 2R fallback, which is a very different trade from the one the setup advertises. Third, the box is a fixed window rather than a real structure, so on a slow grind the engine will keep declaring boxes that nobody was actually defending. And finally there is no chase cap at all: entry is the live quote however far past the edge it has already run, while the stop stays at the breakout bar's low, so arriving late silently inflates R.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

Order Flow Momentum

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	options
Typical session	09:30–16:00 ET on 5-minute bars. In practice no signal before roughly 10:05–10:10 ET. There is no entry cutoff of its own; this strategy is same-day only.

The idea in one sentence

A synthesized buying-pressure line is rising, and price pushes through the higher of the last two swing highs. Buy calls there, stop under the lower of the last two swing lows, target twice the risk.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: A synthesised buying-pressure line is rising and price pushes through the higher of the last two swing highs. Stop under the last two swing lows, target twice the risk.

Setup — a pressure line and a piece of structure

The idea behind this strategy is the oldest one in tape reading: if buyers have been paying the offer for a while and price then clears the last shelf of supply, the people who were selling into that shelf are done and the move continues. The engine expresses that as two separate readings taken from the same 5-minute bars. The first is a cumulative volume delta line, which is meant to say whether aggressive buyers or aggressive sellers have been in control. The second is the recent swing structure — the pivot highs and pivot lows that the last half hour of trading has laid down. Neither reading is a signal on its own; the trade is the moment they agree.

Entry — agreement between the proxy and the structure

On each scan the engine takes the change in the proxy line over the lookback window and asks only whether it is positive or negative. There is no magnitude test at all: one share of net positive delta counts the same as a million. If it is positive, the engine finds the last two confirmed pivot highs and takes the HIGHER of the two as the trigger level; if the live quote is above it, calls are bought at that quote. Negative delta plus price below the LOWER of the last two pivot lows buys puts. The trigger level is therefore genuinely historical structure, not something that just formed.

Stop — the FARTHER of the two recent swing lows

That is deliberately the wider of the two available stops, and it matters more than it sounds: it is what sets R, and R is what sets the target. A long that triggers on a break of a swing high sitting a few cents above recent trade can still be carrying a stop half a percent below, and the 2R target is then a full percent away. The stop is STATIC — computed once at signal time and never recomputed by this engine.

Target — a flat 2R, and what actually closes the trade

The target the engine reports is entry plus twice the entry-to-stop distance on a long, and the mirror on a short. There is no scaling out and no runner. It is worth being precise about what those two underlying prices do in live trading, though, because it is not what most people assume. The underlying stop is not armed as a price trigger. The structure-break exit is scoped to the andre and orb strategies, and the level-invalidation exit is scoped to the levels strategy, so neither reaches this engine's positions. In practice the trade closes when the contract is down 35 percent, up 70 percent, or caught by the global breakeven ratchet.

Where it breaks down

Three ways, and the first is structural. Because the proxy test is a bare sign check, in any session with a mild upward drift the CVD condition is satisfied essentially all day, and the strategy degenerates into 'buy every break of the higher recent swing high' — a plain momentum breakout wearing an order-flow label. Second, the wide stop: taking the deeper of two pivot lows makes R large on exactly the days when structure is messy, and a 2R target measured from a large R is frequently a move the underlying will not make before the close, which for a 0DTE-style contract means theta wins. Third, nothing stops the setup repeating.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

1H Level + Flow Reversal

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	options
Typical session	Scans completed 5-minute bars during the regular session, inside the 09:30-16:00 ET scalp window like the rest of the roster. Its structural zones come from the last 30 days of completed hourly bars. A confirmed setup can stay armed for a stretch while it waits on the next 5-minute candle and fresh order flow before it is dropped as stale.

The idea in one sentence

Trades a rejection off a strong, body-defined 1-hour demand or supply zone, but only after a second 5-minute continuation candle and repeated confirmation from real-time tape and order-book flow.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: The level is a strong 1-hour zone built from candle bodies. A 5-minute rejection arms it, a second candle and live order flow must both agree, and the stop sits beyond the zone's sweep.

Setup -- a body-defined 1-hour zone

The engine watches completed hourly candles for a structure shift: a rejection followed by a close above the last lower swing high builds a demand zone, and the mirror image builds a supply zone. The zone's edges are drawn from candle bodies, because a body shows where price was actually accepted, while the wick beyond it is kept separately as a liquidity sweep rather than folded into the zone itself.

Ranking -- a zone has to earn the right to be traded

Every zone is scored out of 100 on how far price moved away from it, how many times price has reacted off it before, whether it was swept first, and how recently it formed. Weak, old or thin zones are ignored outright; live trading requires a fairly high score before a zone is even eligible for a setup.

Trigger -- rejection, then a second candle that agrees

A completed 5-minute candle has to touch or poke through the zone and close back outside it -- that only arms the setup, it is not the entry. The very next 5-minute candle then has to close even farther away from the zone than the first one did. If it doesn't, the setup is cancelled and the zone goes on cooldown before it can arm again; a single wick by itself never triggers a trade.

Confirmation -- real order flow has to agree twice over

Once price has confirmed with two candles, the engine checks live tape prints, order-flow imbalance and order-book depth at the zone and requires several independent supportive reads before it will actually enter. A quiet, stale, thin or opposing tape resets or blocks the trade -- there is no synthetic stand-in for real flow, so a data outage produces no trade rather than a guess.

Stop, target and where it breaks down

The stop sits beyond the zone or its liquidity sweep, whichever is farther, with a little extra room so a shallow wick doesn't take it out; the initial target is a set multiple of that risk, with a runner managed off further readings of the same live order flow. The honest limits: the 1-hour chart only marks a location, not a guaranteed reversal, so it leans entirely on live order-flow confirmation, and if the data feed backing that confirmation is stale or unavailable the strategy simply produces nothing rather than trading blind.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

Late-Day Momentum Continuation

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	options
Typical session	15:00 ET → 16:00 ET only (one hour a day; nothing else fires)

The idea in one sentence

A stock that has spent the whole session on one side of VWAP coils into a tight box in the last hour. Buy the break of that box, stop at its far side, target the next swing — and be flat by the bell.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: A stock that spent the whole session on one side of VWAP coils in the last hour. The trade buys the break of that box and is flat by the bell.

Setup — a day that already made up its mind

The engine only looks at the market between 15:00 and 16:00 ET. Before that hour it returns nothing at all, no matter how good a chart looks. Inside the hour it asks one question about the whole session so far: what fraction of the day's 5-minute closes printed above session VWAP, and what fraction below. If at least 65% sit on one side the day is called an uptrend or a downtrend; if neither side reaches 65% the symbol is dropped. That is a deliberately crude test, and it is crude on purpose — the strategy is not trying to find a turn, it is trying to identify a day that has already been one-directional and is likely to stay that way into the close as institutional order flow finishes what it started.

Entry — the live quote, not a bar close

The trigger is a bare inequality against the live price: for a long, the current quote trading above the box high (or the day high); for a short, below the box low (or the day low). There is no close-beyond requirement, no volume confirmation and no retest. The scan pulls a batch quote for the whole universe and uses that price as the entry price, falling back to the last 5-minute close if the quote is missing. Because scans run on an interval, the fill price is whatever the quote happened to be when the engine looked — the engine does not cap how far past the level that may be.

Stop — static, at the other side of the structure

When a box exists the stop is simply the box's other edge: the box low on a long, the box high on a short. Because a box is by definition no wider than 0.6% of price, that makes R small and the geometry tight. When there is no box the fallback is much cruder and worth knowing about: the stop becomes the LOWEST swing low of the entire session on a long (the highest swing high on a short), not the most recent one. On a strong trend day that can be a stop several percent away, and the same 2R target is then measured off that much larger R. The stop is computed once at entry and never moves — it is static.

Target — the next level, else two times risk

The engine looks through the day's confirmed swing pivots for the nearest one beyond the entry in the trade's direction — the closest swing high above a long entry, the closest swing low below a short entry — and uses that as the target, on the reasoning that the next place the market already turned is the next place it is likely to pause. If no such pivot exists, which is common when the entry is a break of the day's own high, the target falls back to entry plus two times risk.

Where it breaks down

The obvious failure is the late-day fake: a one-directional day squeezes into a box because the trend is exhausted, not because it is resting, and the break is the last buyer being filled before the reversal. Because there is no retest and no volume test, this strategy takes every one of those. The second failure is quieter and structural. The trade lives entirely inside the window where the bot's own end-of-day profit protection is tightening — from 15:00 a scalp that gives back 20% of its peak is closed, and that fraction shrinks toward 6% as the bell approaches — and everything left over is swept flat at 15:55. So the 2R target frequently never gets a chance to govern the exit, and the strategy's measured behaviour is closer to 'ride the last half hour and get taken out on the first give-back' than the geometry suggests. Third, theta: a 0DTE contract bought at 15:20 has forty minutes of life, so a move that goes nowhere still loses, and the flat -35% premium stop can be hit by decay alone while the underlying sits exactly where you bought it.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

Gamma Level Reaction

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	options
Typical session	09:30–16:00 ET on 5-minute bars. Roughly 09:55–10:00 ET at the earliest, and it also needs a fresh dealer-positioning snapshot, which is refreshed every 15 minutes while the market is open. No entry cutoff of its own.

The idea in one sentence

Dealer-positioning levels — the call wall, the put wall, the gamma flip and max pain — are the strikes market makers have to hedge around. Trade price rejecting off one of them, or accepting through it, targeting the next one.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: The level is one market makers must hedge around -- a call wall, a put wall, the gamma flip. The trade takes the rejection off it, or the acceptance through it.

Setup — why these four prices matter

Options dealers are short the contracts retail and institutions bought, and they hedge that exposure in the underlying. Where open interest is concentrated, their hedge changes fastest, so their buying and selling near those strikes is mechanical rather than opinionated. Price tends to either stall at those strikes, because dealers are leaning against it, or to accelerate through them, because the hedge flips sign. The strategy does not try to predict which; it waits for price to interact with one of the four levels and then trades the interaction it observes.

Entry — nearest level, then rejection or breakout

The engine picks whichever of the available levels is nearest the current price. Given that, two patterns qualify for a long. A REJECTION is price having traded below the level within the lookback window and now being back above it. A BREAKOUT is the previous completed bar having closed at or below the level with price now above it — the crossing bar itself. Shorts are the mirror. When both patterns are true the engine calls it a rejection.

Stop and target — geometry that comes from the levels

On a rejection the stop is the lower of the reaction low and the level itself, which puts it under the wick that probed through. On a breakout the stop IS the level: the thesis is acceptance through it, so a return below kills the idea. Both are STATIC prices, fixed at signal time. The target is the next positioning level in the trade's direction — the next wall or flip or max pain above entry for a long — and only if there is no such level does it fall back to twice the risk. That is faithful to the idea, but it also means the reward is whatever the chain happens to put there, and there is no minimum reward-to-risk check anywhere in this strategy. A rejection that entered a long way above its stop with the next wall only a few cents overhead is a perfectly valid signal to this engine even though the geometry is terrible.

Where it breaks down

Start with the data. The walls are open-interest extremes on one expiry, refreshed every fifteen minutes; they are a reasonable proxy for dealer positioning and nothing more, because this codebase has no transaction-classified options flow and therefore no way to know which side actually opened the interest. Then the reward: because the target is 'the next level' with no minimum, a large number of valid signals carry sub-1R geometry.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

KayCapitals A+ ORB Continuation

Quick fact	What the app says
Usual horizon	scalp
Usual instrument	options
Typical session	09:45 ET earliest (the 15-minute opening range must be complete) -> 11:00 ET last entry -> 15:55 ET blanket scalp flat. Nothing from this engine is ever held overnight.

The idea in one sentence

Wait for price to escape the overnight no-trade zone, then take the FIRST clean continuation after it breaks the opening range the same way -- never on the breakout candle itself, always after a retest that holds and a confirming candle. Profit comes off at a key level, never at a fixed R multiple, because the whole premise is that levels are where the other side's orders sit.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: Price must first escape the overnight zone, then break the opening range the same way. Profit comes off at a level, never at a fixed multiple.

The no-trade zone -- the gate that rejects most bars

Four prices are taken before the open: the premarket high and low, and yesterday's regular-hours high and low. They are not entry levels; they are the walls of a box. While price sits inside that box, both sides still have unfinished business and an opening-range break is just noise inside a bigger box, so nothing is taken at all. Price must CLOSE clear of the zone before any setup counts, and the direction of that escape is the only direction that may be traded that session. This is by a wide margin the most consequential number in the strategy: on a real two-year replay, 83% of every candidate bar was rejected right here, and every other filter only ever sees the remaining 17%. Getting the premarket levels requires an extended-hours feed, and the bot fails CLOSED without one -- a missing premarket high is recorded as unknown, never as zero, because a symbol with no premarket data would otherwise appear to escape the box every single morning.

The opening range, then break, retest, continuation

The first fifteen minutes of regular trading give a high and a low. Nothing may be taken before that range is complete, which is why 09:45 is a structural floor rather than a preference. Then: a break is not an entry. Price has to close beyond the range edge, come BACK and touch it -- within a tolerance measured in ATR, so the touch means the same thing on a quiet day as on a violent one -- and the level has to hold. Only then, on the next confirming candle, is the trade taken. The source rules are unambiguous that the breakout candle itself is never chased, and the bot enforces that twice over: once by requiring the retest at all, and again with a hard gate that refuses any entry sitting more than 0.75 ATR past the trigger, no matter how good the setup looks.

The filters, and the 3-of-5 quality score

A 200-period average on the 5-minute chart is the regime read, and by default it is a hard gate: a long below it, or a short above it, is refused outright. Before that, the engine asks whether price is CHOPPING on the average rather than trending away from it -- the last five closes flipping sides more than twice, or all five sitting within 0.10 ATR of it, magnetised with no room for a continuation leg. Either vetoes the setup. Session VWAP and a bull or bear flag are preferred but not required. Five components are then scored, and only after every mandatory gate has already passed: three of five is the minimum that qualifies. The ordering is the entire point -- a perfect five can never buy its way past a gate, because the score exists to RANK setups that already qualified, not to admit ones that did not. A component whose data is missing counts as unknown, not as false, so a degraded feed produces no trades rather than looser ones.

The stop and the target -- structure, never a percentage

There is no percentage stop anywhere in this strategy. The stop is whichever of four structural prices is nearest: the far side of the flag, the retest's own invalidation swing, the key level that broke and is now support or resistance, or re-entry into the opening range. Each is padded by 0.05 ATR so a wick that only kisses the level does not take it out. If every rung is unusable the trade is refused rather than falling back to a percentage. The target is the nearest key level ahead of the entry that is at least twice the risk away, and only levels that can actually act against the trade count. If no level qualifies, the trade is REJECTED -- manufacturing a target at twice the risk would convert this into a fixed-R system wearing a level-shaped costume, and every number measured after that would describe a different strategy.

Managing it, and where it breaks down

Half the position comes off at the first target, the stop moves to breakeven, and from there a trail follows the most recent confirmed swing behind price, taking the TIGHTER of the old and new stop so it can never widen. A position that has not made a quarter of its risk back within twenty minutes is closed at the market: this is a continuation trade, and if the continuation has not happened, waiting longer is hoping. Everything is flat by 15:55 and nothing is held overnight. Where it struggles: it is extremely sensitive to premarket data quality and fails closed, so a feed gap looks identical to a quiet market. It needs a symbol that HAS a meaningful premarket session, which is why the universe is index ETFs rather than single names. And the 200-period average needs about 2.6 sessions of history, so a cold start genuinely has no answer for the first two and a half days.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

Swing — Trend Pullback

Quick fact	What the app says
Usual horizon	swing
Usual instrument	both
Typical session	Signals come from the nightly scan of completed daily and hourly bars, not from watching price during the day. The roster window defaults to 09:30-16:00 ET but can be narrowed, and once a position is open it can be held overnight for two to ten trading days.

The idea in one sentence

Continuation after a controlled ATR pullback inside an established daily trend, confirmed by the latest hourly move.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: The trend and the pullback are measured on daily bars, the confirmation on the hourly. Held for days: stop 1.5 ATR away, target twice the risk, closed after ten days regardless.

Setup -- find the trend

The daily close has to sit above both a fast and a slow moving average, with the fast one still above the slow one -- for a short, the ordering flips the other way. That ordering is the whole regime read: this strategy has no view on stocks that are consolidating or in the middle of choosing a direction, only on ones already moving one way on the daily chart.

Entry -- a controlled pullback, then an hourly confirmation

Price is allowed to pull back toward the fast moving average, but only up to one and a half times the daily ATR -- anything looser is skipped as too extended to call a controlled pullback. The trade isn't taken on the pullback itself: the most recently completed hourly candle also has to close back in the direction of the daily trend before entry is confirmed.

Stop, target and the clock

The stop sits one and a half ATR beyond the signal close, and the initial target sits three ATR beyond it -- twice the risk. If neither has been hit, the position is closed automatically after ten trading days rather than left open indefinitely; live management can close it sooner through the same overnight swing exit process the other swing strategies use.

Where it breaks down

A pullback can qualify even in a market-wide selloff -- there is no separate market-regime guard on top of the trend filter yet. The pullback check only asks whether price came close enough to the moving average, not whether it actually touched it, so a shallow dip can still qualify. And because this is a swing position, a stop is only a price: an overnight gap through it exits at whatever the next open prints, not at the stop itself.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

Swing — 52-Week High Breakout

Quick fact	What the app says
Usual horizon	swing
Usual instrument	both
Typical session	Signals come from the nightly scan of completed daily bars, not from watching price during the day. The roster window defaults to 09:30-16:00 ET but can be narrowed, and once a position is open it can be held overnight for two to ten trading days.

The idea in one sentence

Buys a 20-day price breakout that happens near the 52-week high, once daily relative volume confirms real participation.



Educational setup drawing. The dashed levels show entry, stop, and take-profit logic; actual prices and fills vary.

What must happen before entry: The range is the last 20 sessions, broken near the 52-week high on heavy volume. Stop one ATR under the broken level, target three ATR, ten-day time limit.

Setup -- staying near the yearly high

The stock's daily close has to sit within three percent of its trailing 52-week high before anything else is checked. That is a location filter, not a trigger: it narrows the universe down to names already near their best levels of the year, where a breakout is most likely to mean something rather than just be noise.

Trigger -- clearing the last 20 sessions on real volume

The completed daily close has to equal or exceed the highest high of the prior 20 trading sessions, and daily volume has to run at least one and a half times its own 20-day average on the breakout day. A breakout on light volume is skipped outright -- the strategy wants real participation behind the move, not a low-volume drift through the level.

Stop, target and the clock

The stop is set at the prior 20-session high minus one ATR, fixed the moment the breakout is recognized. The initial target sits three ATR above the signal close -- roughly twice the risk. If the trade hasn't resolved either way within ten trading days it is closed automatically; live management can close it sooner through the same overnight swing exit process the other swing strategies use.


Where it breaks down

Only bullish breakouts exist today -- there is no short side to this strategy yet. A tight base is preferred but a loose, sloppy one is not actually blocked from qualifying. And because this is an overnight position, the stop is only a price: a gap through it at the next open exits at whatever that open prints, not at the stop itself.

Beginner decision: if you cannot explain the setup, stop, and exit in your own words, turn this signal type off until you can.

SCREEN WALKTHROUGH

Long Term overview




Long Term is a separate portfolio workspace. It does not listen for or copy Andre's signals.

What to look for

1. Set a capital partition before creating a long-term opening proposal.
2. A 25% Long Term allocation leaves 75% for copied/short-term sizing.
3. The partition is a software limit inside one Schwab account, not a new broker subaccount.
4. Approval is required by default.

SCREEN WALKTHROUGH

Long Term tools and research



Long Term can research, scan, and prepare proposals; research alone does not place an order.

What to look for

1. Use ticker research or a watchlist scan to collect information.
2. Sector Rotation ranks areas of the market; it does not guarantee leadership will continue.
3. Review every proposal's side, quantity, estimated price, and reason.
4. Buy, add, trim, exit, and covered-call proposals must pass fresh broker and partition checks.

Long Term actions in plain language

Action	Meaning and beginner warning
Buy / open	Start a new long-term stock or LEAP position. Confirm the capital partition and maximum dollar commitment.
Add	Increase an existing holding. Adding to a losing position increases risk; it does not repair the original decision.
Trim	Sell part, but not all, of a holding. Verify the remaining shares or contracts after the fill.
Exit	Close the entire selected long-term holding.
Covered call	Sell a call against shares already owned. One contract normally obligates 100 shares and can cap upside.
Sector rotation	Compare sector leadership and prepare research. Rankings are backward-looking observations, not assured future returns.

Optional AI

Long Term works with No AI. If OpenAI or Anthropic is selected, the subscriber supplies and pays for their own provider key. Ollama runs locally but uses disk, memory, CPU/GPU time, and electricity. AI output is research text, not permission to trade.

Never approve an order merely because an AI explanation sounds confident. Verify symbol, instrument, expiration, quantity, limit price, partition, buying power, and downside independently.

Position Doctor permissions and publisher close-only

The copier includes the supported stock add/trim decision order from the main Long Term Position Doctor. It is deliberately narrower than the main engine: unsupported rolls, collars, spread conversions, and short-option changes remain advisory instead of being approximated.

The subscriber chooses exactly what may run

1. Allow automatic purchases/adds is a separate switch from automatic trims.
2. A dollar cap limits one Doctor purchase; a percentage limits one trim.
3. A per-review order cap limits how many Doctor actions may be submitted.
4. Both permissions default OFF and remain inert until the real-money acknowledgment is checked.
5. Doctor orders run only during regular New York market hours and still recheck quotes, spread, buying power, owned shares, and the Long Term capital partition.

An empty watchlist or a holding with no completed research produces HOLD, not a guessed trim. The Doctor never treats missing data as permission to trade.

Andre's master access switch

The publisher sends a signed, encrypted status command addressed only to this device. While access is active, the subscriber may receive eligible signals and may separately opt into Doctor automation. If Andre switches the subscriber off or removes the last signal grant, the command is persisted on this computer and the entire copier changes to **CLOSE-ONLY**, including after restart.

Close-only still allows	Close-only blocks
Publisher exits for positions already held; subscriber trim and close actions; emergency control and flatten; broker reconciliation.	Copied entries; Long Term buys/adds; Position Doctor automation; covered-call openings; schema-v2 multi-leg entries; pending buy approvals.

The publisher page refuses to record a shutoff when it cannot first deliver the private close-only command. This prevents the dangerous split state where signals stop but local Long Term automation keeps buying.

Set up optional AI for Long Term

The Long Term page can work with **No AI**. In that mode, ordinary portfolio controls and rule-based research remain available; the provider test reports **Rule-based analysis only**. Connecting an LLM adds a written deep-review layer to ticker research and watchlist scans. It does not connect Schwab, choose the capital partition, approve an order, or make AI output true.

Each subscriber uses their own OpenAI or Anthropic account and pays that provider directly. Andre does not provide, receive, recover, or maintain subscriber API keys. Ollama is the private local alternative and has no per-call provider bill, but it uses the subscriber's computer resources.

Choose one setup

Choice	Best fit, cost, and trade-off
No AI	Simplest and safest starting point. No provider account or API key. Long Term uses rule-based analysis only.
OpenAI	Cloud AI. Requires the subscriber's own API account, API billing or credits, and an API key. Usage is billed by OpenAI.
Anthropic	Cloud AI. Requires the subscriber's own Anthropic Console account, API billing or credits, and an API key. Usage is billed by Anthropic.
Ollama (local)	Runs a downloaded model on this computer. No cloud API key and no per-call provider charge, but setup is more technical and uses disk, memory, CPU/GPU, and electricity.

A ChatGPT or Claude consumer subscription does not automatically supply API credits. **OpenAI API billing is separate** from ChatGPT billing, and **Anthropic API billing is separate** from a Claude subscription. Provider rules and prices can change; check the provider's own billing page before use.

Find the controls in the copier

1. Open the Trading Copier and choose **Long Term** in the top navigation.
2. Scroll to **2. Connect your own optional LLM**.
3. Choose Provider, enter the exact Model name, and enter the API key only when using OpenAI or Anthropic.
4. For Ollama, enter the local URL and exact downloaded model name. No API key is used.
5. For a paid provider, tick the direct-billing acknowledgment, then press **Save provider**.
6. Press **Test connection**. Do not run a deep scan until the app confirms Connected.

OpenAI setup

Do this on the subscriber's own computer and account. The API key is a password for paid API usage; it is not the subscriber's ChatGPT password.

1. Go to the official OpenAI developer platform: https://platform.openai.com/
2. Sign in or create the subscriber's own OpenAI account.
3. Open Billing and add a payment method or prepaid credits if the account requires them. Set a usage budget or alert when available.
4. Open API keys and create a new secret key for the copier. Give it a recognizable name such as Trading Copier Long Term.
5. Copy the secret immediately. The provider may show the complete value only once.
6. In Copier > Long Term > Connect your own optional LLM, choose **OpenAI**.
7. Model may be left blank to use the copier default **gpt-4o-mini**, or enter an exact model name that the subscriber's API account can use.
8. Paste the key into **API key (write-only)**, tick the billing acknowledgment, press Save provider, then press Test connection.

The saved secret is write-only: the page does not display it again. Leaving the key field blank during a later save keeps the existing saved key.

Official account and key instructions can change. If the provider's current page differs from these labels, follow OpenAI's current API-key and billing documentation at https://platform.openai.com/docs/ and https://help.openai.com/.

What success looks like

1. Test connection returns Connected and identifies OpenAI and the model.
2. A one-ticker deep review returns research text without an authentication or billing error.
3. The subscriber can see the request in their own provider usage dashboard.

Anthropic setup

The Anthropic API key is also a paid-service credential. It is not the subscriber's Claude login password and should never be shared.

1. Go to the official Anthropic Console: https://console.anthropic.com/
2. Sign in or create the subscriber's own account.
3. Open billing or plans, add credits/payment if required, and configure a spending limit when available.
4. Open API Keys and create a key for Trading Copier Long Term.
5. Copy the key when it is shown.
6. In Copier > Long Term > Connect your own optional LLM, choose **Anthropic**.
7. Model may be left blank to use the copier default **claude-3-5-haiku-latest**, or enter an exact model name available to that API account.
8. Paste the key into API key (write-only), tick the billing acknowledgment, press Save provider, then press Test connection.

If Anthropic retires or renames a model, enter a currently supported exact model name from Anthropic's documentation. The copier will not silently choose a different provider.

Current official starting points: https://docs.anthropic.com/ and https://console.anthropic.com/settings/keys

Ollama local setup

Ollama keeps LLM requests on the subscriber's computer. It is appropriate for someone who prefers a local model and is comfortable installing and maintaining it. The copier deliberately accepts only a loopback address, which prevents pointing this feature at another computer or an internet-exposed Ollama service.

1. Download Ollama from the official site: https://ollama.com/download and install the version for Windows or macOS.
2. Open Terminal or PowerShell once and download a model. For the copier default, run: **ollama pull llama3.2**
3. Confirm Ollama is running. Its normal local address is **http://127.0.0.1:11434**.
4. In Copier > Long Term, choose **Ollama (local)**.
5. Model may be left blank for the copier default **llama3.2**. If a different model was pulled, enter that exact local name.
6. Keep the Ollama local URL at http://127.0.0.1:11434 unless the subscriber intentionally changed the local port.
7. Press Save provider and Test connection. No API key or paid-provider acknowledgment is required.

Do not configure router port forwarding or expose Ollama to the public internet. The copier accepts only localhost or another loopback IP for this feature.

A first model download can be large and a first response can be slow while the model loads. Official installation and model instructions: https://ollama.com/download and https://ollama.com/library

Use AI safely and control cost

Start with a one-ticker test

1. Confirm Test connection says Connected.
2. Under Research a ticker, enter one familiar symbol.
3. First run ordinary research without Deep AI review and read the rule-based result.
4. Then tick Deep AI review and run the same symbol once.
5. Compare the added narrative with broker facts, filings, and the proposal details. AI can be stale, incomplete, or wrong.

Understand the bill before a watchlist scan

Deep watchlist mode can make **one paid call per ticker**. Ten symbols can mean ten provider calls. Begin with one symbol, inspect the provider usage dashboard, set provider-side budgets or limits, and use a lower-cost model when appropriate. Turn Provider to No AI when deep reviews are not needed.

The LLM cannot authorize a trade

Research produces information and may help prepare a proposal. Approval remains required by default. The subscriber must independently verify the symbol, shares or option contract, expiration, quantity, estimated limit, maximum commitment, buying power, and downside. Automatic Long Term execution is a separate override and should remain off for a beginner.

Protect and replace the key

1. Never send the API key to Andre by email, text, screenshot, or device code.
2. Never enter Andre's or another subscriber's API key. Each subscriber owns their account, bill, limits, and key.
3. Use **Delete saved key** to remove the cloud key from this copier. The provider is changed to No AI.
4. Also revoke an exposed or unused key in the provider console. Removing it only from the copier does not revoke the provider credential.
5. To replace a key, revoke the old provider key, create a new one, paste it into the write-only field, save, and test.


LLM troubleshooting

Message or symptom	What the subscriber should check
API key is not configured	Choose the intended cloud provider, paste that provider's key, acknowledge billing, Save provider, and Test connection.
HTTP 401, 402, or 403	Usually credentials, account access, or billing. Confirm the provider matches the key, billing/credits are active, and the key was copied completely. Replace rather than repeatedly reusing an exposed key.
HTTP 404 / model error	Enter the exact model identifier available to that API account. A consumer-app model label may not be an API model identifier.
HTTP 429	The provider rate or spending limit was reached. Wait, reduce calls, check credits and limits, or contact the provider. Do not keep pressing the scan button.
Provider unavailable	Check internet access, provider status, firewall/VPN, and system date/time. The app intentionally hides secret details from errors.
Ollama connection refused	Start Ollama, confirm the model was pulled, keep the URL on localhost, and test http://127.0.0.1:11434 locally.
Ollama model not found	Run ollama list, copy the exact installed model name into the Model field, save, and test again.
Deep scan seems expensive	Stop the scan, reduce the watchlist, use ordinary research or No AI, and inspect the subscriber's provider usage dashboard.

If Test connection fails, Long Term should stay on No AI until the subscriber understands and corrects the problem. A failed AI connection is not a reason to change Schwab credentials or reconnect the device code.

SCREEN WALKTHROUGH

My Results




My Results is the subscriber's local trading journal and summary.

What to look for

1. Review closed trades and realized outcomes.
2. Filter by strategy or symbol when comparing behavior.
3. Exported history is a record, not proof that a strategy will remain profitable.
4. Schwab remains the final source of truth for official orders, fills, balances, and tax documents.

SCREEN WALKTHROUGH

System Map



System Map explains the boundaries: Andre publishes encrypted messages; this computer decrypts and controls its own Schwab account.

What to look for

1. Andre's side does not receive the subscriber's private key.
2. Only this device can open messages encrypted to its public key.
3. The local risk gate runs before a new entry.
4. The broker's response and position reconciliation are authoritative.

Daily, weekly, and emergency routines

Before the market each day

1. Start the copier and keep the computer awake.
2. Home: verify Signals from Andre is Connected.
3. Home: verify Schwab is Connected to the intended masked account.
4. Confirm Approve first unless automatic buying is intentionally enabled.
5. Review limits and active Signal Types.
6. Open Alerts. Every part under Is it running? should say Running, and Positions left with no stop should be zero.
7. Clear anything left over: a position Short Term does not recognise, or an order that was never confirmed. New buying stays paused until you answer the first of those.
8. If you will be away from the screen, press Turn the alert sound on once so the waiting-trade alarm is not mute.
9. Open Schwab separately and confirm buying power and existing positions.

Every week

1. Press Reconnect Schwab before the countdown expires.
2. Sign in on Schwab's site and approve access.
3. Confirm Home returns to Connected with roughly seven days remaining.
4. Install a newer copier build when the official page announces one; preserve the existing identity.

If something looks wrong

1. Stop approving new entries.
2. Open Alerts and read the newest entries first.
3. Open Schwab Orders and Positions.
4. Close or reduce a real position directly if necessary.
5. Use Done for the day to block new entries.
6. Save a redacted screenshot and the agent.log file for support.

Closing the browser tab does not quit the copier. Use Quit Copier in the footer. Done for the day blocks new entries but keeps exits active.

Emergency takeover and flatten

Emergency control is different from Done for the day. It writes a durable account interlock before touching an order. The interlock survives restart and prevents new entries, publisher exits, schema-v2 commands, Long Term automatic orders, and stop repair until you explicitly resume.

Control	What it does
Done for the day	Blocks new entries until the next market open. Normal stops and exits remain active.
Take manual control	Freezes automation and cancels recorded protective stops, but submits no sell. Use before managing positions directly in Schwab.
Emergency flatten	Freezes automation first, cancels and confirms recorded stops, then sends urgent closes for tracked positions.
Resume automation	Returns order authority only after you confirm that Schwab positions and open orders were checked.

Take manual control

1. Open Home and press Emergency control.
2. Choose Take manual control and tick its confirmation.
3. Wait for every recorded protective stop to show confirmed inactive.
4. Open Schwab Orders and Positions and independently verify the cancellations.
5. Manage the remaining positions in Schwab. The copier stays hands-off across restarts.
6. Return to Emergency control and resume only after checking the complete account.

Emergency flatten

1. The emergency interlock is saved before any cancellation or sale.
2. Each single-position stop is canceled and broker-confirmed before its urgent close.
3. Two- and four-leg schema-v2 groups close with one broker-native atomic complex order; they are never legged out.
4. Missing contracts, unequal ratios, unreadable order status, or ambiguous broker responses stop or quarantine that position instead of guessing.
5. A submitted order is not reported as filled. Verify all final fills and remaining positions in Schwab.
6. The copier remains emergency-stopped after the attempts, even when everything appears flat.


Emergency single-position closes use an immediately marketable limit when a quote is available. If no usable quote exists, the existing emergency path may use a market order. Price can be substantially worse than the last displayed value.

Live View - watch what the copier sees

Open **Live View** in the copier's top menu (the /live page of your local control panel, next to My results). It is the same "what the bot sees" screen Andre's engine uses, narrating YOUR copy of each trade in real time. It appears with copier 0.15.0 or newer - if the link is missing, update first.

What the screen shows

1. The price chart for the symbol in focus, drawn from your own Schwab market data in 5-minute candles.
1. Andre's intent on the chart the moment a signal arrives: the leader entry level, the stop, and the target.
1. A running thought feed of every decision in order: signal received (signature verified), your signal-type filter, done-for-the-day, trading hours, the day-trade margin guard, sizing, then the approval wait, the order, and the fill.
1. Your open trade card - contract, quantity, average cost - and markers on the chart where your fills happened.
1. Freshness chips that wear the age of the data: a healthy live stream keeps them fresh, a stalled one visibly goes stale.



Live View: the chart with the leader's levels, the thought feed, and the single Take Profit button.

The one button: Take Profit

Everything on this screen is read-only by design, except one green **Take Profit** button. Pressing it sells your ENTIRE position in that symbol through the copier's normal exit path - the same order ladder, journaling, and profit-and-loss booking as every other close. It is not a new way to place orders.

1. A confirm card first shows the exact order, the estimated fill, and the estimated realized profit or loss.
1. This is a real account, so you must type the quantity to confirm. A wrong number refuses the order.

1. If your position changed or the price moved since the preview, the copier refuses and asks you to re-open the confirm. That refusal is protection working, not a bug.
1. Position sizing stays with the bot. There is no add, no trim, and no manual open here, and a tampered page cannot unlock one - the server refuses any action this build does not offer.
1. Stock (share) positions are closed from the Positions page instead; Live View's per-contract dollar math is for options.

If something looks wrong

Live View is a window, never a driver. If the chart is empty, the feed stalls, or the page shows an error, the copier itself keeps polling, gating, and trading exactly as before - close the tab and reopen it whenever you like. A problem on this screen never blocks an exit: Andre's exits and all of your other controls keep working unaffected.

Atomic multi-leg option groups

Version 0.16.8 keeps every schema v1 single-contract workflow and adds schema v2 for complete two-leg and four-leg option position groups. A group is one risk-defined position. The copier never turns it into separate single-leg trades.

Current release boundary

Schema-v2 **paper** signals are authenticated, validated, simulated, persisted, and displayed. They call zero broker methods. The destination is also live-capable, but live is default OFF and requires the independent Live schema-v2 multi-leg switch plus Auto execute acknowledgement. The copier rechecks entitlement, broker capability, exact contracts, quotes, market hours, account permission, buying power, and maximum loss immediately before sending every leg in **one native complex-order** request. It never submits legs one at a time.

Badge	Meaning
PAPER	Complete group simulation only; the broker is never called.
LIVE	Default OFF. Requires entitlement, Auto execute acknowledgement, the separate live multi-leg switch, option permission, exact contracts, and local risk capacity.
schema v1	Existing single stock or single option behavior remains unchanged.
schema v2	Two-leg vertical or four-leg iron structure; never downgraded to v1.

Safety rules that cannot be bypassed

1. No sequential legging and no market-order entry.
1. No expiry, strike, right, ratio, multiplier, or contract substitution.
1. A missing protective wing rejects the complete signal.
1. Unknown schema versions, structures, actions, or intents are recorded as rejected; nothing is guessed.
1. Stale, crossed, incomplete, expired, or economically inconsistent groups are rejected.
1. Duplicate event, signal, and group IDs cannot create a second group.
1. An ambiguous response stops in UNCERTAIN. Unequal or partial legs cancel the complete working order when possible and quarantine the group; no retry or independent leg is allowed.

Supported structures and leg map

Labels and action names matter more than color. Long/protective legs are marked BUY; short/premium legs are marked SELL.

Structure	Required strike geometry and opening legs
Bull-put credit vertical	LOW: BUY_TO_OPEN long put | HIGH: SELL_TO_OPEN short put
Bear-call credit vertical	LOW: SELL_TO_OPEN short call | HIGH: BUY_TO_OPEN long call
Bull-call debit vertical	LOW: BUY_TO_OPEN long call | HIGH: SELL_TO_OPEN short call
Bear-put debit vertical	LOW: SELL_TO_OPEN short put | HIGH: BUY_TO_OPEN long put
Iron condor	long put < short put < short call < long call; all four legs required
Iron butterfly	long put < shared short center < long call; both short rights at center

Two-leg diagram

LOWER STRIKE	HIGHER STRIKE
BUY long protective put	SELL short put
6395 PUT / BUY_TO_OPEN	6400 PUT / SELL_TO_OPEN

BULL-PUT CREDIT VERTICAL: the lower long put is the protective wing. If either contract is missing, duplicated, or has the wrong expiry, the entire group is rejected.

Four-leg diagram

LONG PUT	SHORT PUT | SHORT CALL | LONG CALL
BUY wing below	SELL inner put | SELL inner call | BUY wing above
6390 P	6395 P < 6405 C < 6410 C

IRON CONDOR: the strikes must remain in strict order and every leg must share the same underlying and expiry.

Net prices, actions, and risk display

Lifecycle	Native group order	Long-leg action	Short-leg action
Credit open	NET_CREDIT	BUY_TO_OPEN	SELL_TO_OPEN
Credit close	NET_DEBIT	SELL_TO_CLOSE	BUY_TO_CLOSE
Debit open	NET_DEBIT	BUY_TO_OPEN	SELL_TO_OPEN
Debit close	NET_CREDIT	SELL_TO_CLOSE	BUY_TO_CLOSE

All net prices are positive USD-per-share magnitudes. Option cash equals net price x multiplier x group quantity. A negative or zero limit is invalid; the copier never infers debit or credit from a sign.

What the group card shows

1. Strategy, underlying, structure, expiry, PAPER/LIVE badge, and group state.
2. Every OCC contract, option right, strike, open/close action, ratio, and leg status.
3. Group quantity, NET_CREDIT or NET_DEBIT limit, multiplier, and quote age.
4. Maximum gain, maximum loss, and buying-power reservation recomputed from the structure.
5. Forced-exit time, settlement warning, and durable rejection or reconciliation detail.

Maximum gain and loss are per complete group. Quantity multiplies the complete structure. Never multiply only one leg when checking exposure.

Multi-leg workflow and status runbook

1. Publisher creates an explicit schema-v2 group; it does not pass through v1 normalization.
2. Publisher filters by strategy entitlement, schema-v2 capability, maximum legs, and live permission.
3. Subscriber verifies the signature, decrypts, claims the event idempotently, and validates the complete structure.
4. Paper mode simulates and stores every leg in one transaction, then shows one group card.
5. Live mode persists the child/account mapping before one native complex submission; broker acceptance is not called a fill.
6. After fills or restart, the copier reconciles exact holdings and working orders. Only complete equal leg ratios may become OPEN.
7. A group exit reverses the account's actual reconciled remaining quantity atomically. No per-leg buttons are offered.

State	Meaning and trader action
PENDING_APPROVAL	Complete group is waiting for a deliberate review; approving applies to the group.
OPENING	One native complex order would be in progress. Do not submit another.
OPEN	Complete group is held and monitored as one position.
CLOSING	Whole-group closing order is in progress.
CLOSED	All verified group quantity is closed.
REJECTED	Nothing was traded; read the human-readable reason.
PARTIAL_UNWIND	A partial-fill recovery is underway; do not add exposure.
QUARANTINED	Broker facts disagree with the package. New action on this child stops until reviewed.
UNCERTAIN	Stop. Inspect Schwab orders and positions; never retry or trade an individual leg.

Common rejection and recovery cases

1. Unsupported account or permissions: no order; confirm complex-options approval with the broker.
1. Unresolved exact contract or missing wing: reject the complete group.
1. Stale/crossed quote or expired event: reject; do not refresh into a different trade.
1. Buying-power or risk mismatch: reject; reduce risk at the source rather than deleting a wing.
1. Duplicate event: show the prior outcome; never submit twice.
1. Position mismatch or ambiguous submission: mark UNCERTAIN and reconcile against broker truth.
1. Restart during a transitional live state: recover open orders, order history, and holdings before processing another event.
1. Missed forced exit: treat as an emergency; inspect and close the complete verified group in Schwab.

Live controls and broker capability matrix

Installing or updating the copier never enables schema-v2 live execution. Existing keys, device identity, Schwab tokens, and durable child mappings are preserved, while the new live switch starts OFF. Every supported live entry and exit uses a native complex-order.

Required local switches

1. Options are allowed for the account.
2. Automatic execution is selected and its real-money acknowledgement is checked.
3. Allow live schema-v2 multi-leg complex orders is checked separately.
4. The strategy is not muted and the publisher entitlement allows this device.
5. The account passes quantity, loss, buying-power, open-position, hours, TTL, and quote checks.

Broker capability	Required behavior
Atomic complex order	One request contains all 2 or 4 legs; otherwise UNSUPPORTED_STRUCTURE.
Maximum legs	At least the exact requested count; no truncation.
Order types	NET_DEBIT and NET_CREDIT DAY limit orders.
Cancel/replace	Only the complete complex order may be cancelled or repriced.
Reconciliation	Read exact orders, fills, working orders, and positions after ambiguity or restart.
Current Schwab adapter	Vertical debit/credit and four-leg iron/custom packages; account approval still governs acceptance.

A broker or account that cannot support the exact structure receives UNSUPPORTED_STRUCTURE. The copier never simplifies it, changes contracts, or falls back to schema v1.

Restart, partial fill, and quarantine recovery

Automatic restart drill

1. Load every durable live child group and its parent/event/account identifiers.
2. Fetch broker working orders, order history, and exact OCC positions.
3. Compare every leg's side, contract, requested fill, remaining quantity, and group ratio.
4. Mark OPEN only when broker facts prove a complete equal-ratio group; mark CLOSED only when every leg is zero.
5. If a complex order is still working, retain WORKING and never resubmit.
6. If any leg is missing, manually altered, unequal, or ambiguous, cancel the complete working order when possible and QUARANTINE the child.

Partial fills

The copier does not add a missing leg. It cancels or replaces only the broker's complete complex order. A complete partial group ratio may be managed as that smaller verified quantity; unequal fills cannot be treated as a position group and require broker/operator review.

Durable acknowledgement milestones

1. LIVE_SUBMITTED means the broker accepted the request, not that it filled.
2. LIVE_OPEN means reconciliation proved all requested child legs and ratios.
3. LIVE_CLOSING means one complete reversing complex order was accepted.
4. LIVE_CLOSED means reconciliation proved zero remaining legs.
5. LIVE_QUARANTINED or LIVE_UNCERTAIN means stop and compare Schwab; no duplicate submission is allowed.

Qualification checklist before real money

Code completion is not live readiness. Keep the live switch OFF until every applicable structure and broker passes the evidence sequence below.

1. Unit and contract tests: validation, geometry, economics, idempotency, persistence, and v1/v2 separation.
2. Broker sandbox/paper: atomic entry and broker acknowledgement for every supported 2-leg and 4-leg structure.
3. Restart drill: stop after submission and after fill; restart and prove no duplicate order and correct child recovery.
4. Complete-group exit: reverse actual child fills and reconcile every leg to zero.
5. Partial-fill drill: cancel the whole working package and prove no independent leg submission.
6. Shadow live reception: receive real live envelopes with submission disabled and compare all gates/reports.
7. Operator approval: retain screenshots, broker IDs, child IDs, acknowledgements, timestamps, and reconciliation evidence.
8. Limited live canary: explicitly enable one approved account/structure/quantity, monitor it end to end, then review before expanding.

Any stale reconciliation, missing report, unsupported structure, unexpected fill, or unexplained loss disables new schema-v2 live entries until reviewed.

Troubleshooting

What you see	What to do
Waiting for Andre	Leave it open for one minute. Andre must link the exact current TV1- code and send the private connection check. Do not create another identity during an update.
Connected but button still says Connect Schwab	Trust the green connected status. The button is available for reconnection. Continue to the next setup step or Home.
Trying to connect / zero checks	Verify internet access and that the copier process is still running. It retries every 20 seconds.
No new signal	First confirm the private connection check. Then remember: only a new live filled short-term trade is eligible. Paper and Long Term activity are ignored.
Schwab expired	Reconnect immediately. Inspect Schwab directly if a position is open.
Uncertain order	Do not retry. Inspect Schwab Orders and Positions first.
Mac SSL time warning	Update macOS and certificates, enable automatic Date & Time, restart, and do not rely on a custom hours window until the warning clears.
PowerShell window flashes	Install the current packaged build and use its shortcut. Quit older copier processes so scheduled or legacy launchers are not competing.
Mac bad CPU type	Delete the file and download the other Mac architecture.
No such file	Check Downloads and remove a (1) filename suffix by downloading once cleanly.
New buying is paused	A holding in your Schwab account needs an answer. Open Short Term and press Look after it or Leave it alone. Everything you already hold keeps being managed while you decide, and neither button buys or sells anything.
A part of the program says Stopped or Stuck	Open Alerts and read Is it running? to see what has stopped. Close the program and start it again. If it happens twice, save agent.log and send it to Andre.
You missed a trade today	Nothing was bought and no money was lost. Tick the message off. If it keeps happening, read the chapter on who presses the button before changing anything.
Positions left with no stop is not zero	Open your Schwab app and look at that position yourself. The program tries to put a protective stop back on its own and says so when it does; do not wait for it if real money is exposed.
No sound when a trade is waiting	Browsers refuse to make a noise on a page nobody has clicked yet. Press Turn the alert sound on in the banner, early in the day.
Signals that arrived too late to trade	Shown on Alerts. A trade older than about fifteen minutes cannot be opened. If this is not zero on a normal day, check your internet connection and that the computer stays awake.

If a real position is open and the app is confusing, Schwab is the source of truth. Protect the account first; troubleshoot second.

Glossary

Word	Meaning
0DTE	An option expiring today. It can move or lose value extremely quickly.
Alert	Something the program has written down so it cannot be lost. Important ones stay on screen until you tick them off.
Buying power	The broker's estimate of funds available for new positions.
Callback URL	The local address Schwab returns to after authorization.
Covered call	A short call backed by enough owned shares, normally 100 shares per contract.
Device code	The safe-to-share TV1- code containing a device ID and public key.
Fill	Broker confirmation that an order executed.
Limit order	An order that will not pay above or sell below a specified price, but may never fill.
Long / short	Long generally benefits from a rise; short or bearish exposure generally benefits from a fall.
Not managed	A holding the program has been told not to touch. It stays in your Schwab account and is entirely yours.
Premium	The price of an option; standard quotes are per share, normally multiplied by 100.
R	The planned loss distance from entry to stop.
Slippage	The difference between expected and actual fill price.
Stop	A planned loss exit. Fast markets can fill worse than the stop level.
Strategy	A repeatable set of conditions for setup, entry, stop, and exit.
Too old to buy	One of Andre's trades that is now more than about fifteen minutes old. Approving it does nothing.
Unconfirmed order	An order Schwab never confirmed. The program will not retry; you answer it on Short Term.
TV1- code	The copier's public connection code. It is not the private key.
VWAP	Volume-weighted average price, a common intraday reference line.

APPENDIX

Security and support checklist

Never share

1. Schwab username or password
1. Schwab App Secret
1. OAuth callback authorization code or refresh authorization
1. The copier private key or secrets.json fallback
1. Remote-control access while Schwab is open

Safe to share for support

1. The complete TV1- public device code
1. A screenshot with account numbers, balances, keys, and personal information redacted
1. agent.log when specifically requested and reviewed for sensitive information

Local storage

```
Windows: C:\Users\<you>\.trading-copier\
macOS: ~/.trading-copier/
```

settings.db is the authority for subscriber preferences and local control flags. state.db is the authority for positions, orders, approvals, and alerts. A legacy agent.json, account_snapshot.json, day_session.json, or emergency_control.json may remain as an untouched rollback snapshot after upgrading. secrets.json appears only when the operating-system password vault is unavailable. This folder preserves identity and settings across normal upgrades. Back it up securely. Do not email it.

Trading Copier Installation Guide and User Manual. Revised 28 August 2026 for version 0.16.8, application schema v1 and multi-leg schema v2. Source: build_user_manual.py. The software and this document are provided as-is, without warranty. Nothing here is investment advice. Trading involves risk of loss.

Copyright 2026 Walkers Software LLC. All rights reserved.

APPENDIX

Authoritative investor references

The strategy chapters describe the copier's own current rules. For general securities and options education, use these independent regulator and broker resources:

1. SEC Investor.gov - An Introduction to Options:
   https://www.investor.gov/introduction-investing/general-resources/news-alerts/alerts-bulletins/investor-bulletins-63
1. FINRA - Options:
   https://www.finra.org/investors/investing/investment-products/options
1. FINRA - Order Types:
   https://www.finra.org/investors/investing/investment-products/stocks/order-types
1. FINRA - Stop Orders in Volatile Markets:
   https://www.finra.org/investors/insights/stop-orders-factors-consider-during-volatile-markets
1. Charles Schwab - Basic Call and Put Options Strategies:
   https://www.schwab.com/learn/story/basic-call-and-put-options-strategies

Read the current Characteristics and Risks of Standardized Options disclosure supplied by the broker before trading options. Provider pages, costs, approval rules, and product availability can change; the linked official source wins over this manual.